BIDDING REQUIREMENTS for PURCHASING

NOTICE AND INFORMATION FOR BIDDERS

Attachment A: Bid Breakdown & Schedule

Bidder:

DASNY Contact: Susan Valente - svalente@dasny.org

Services/Product Required By: November 30, 2023

Description: Furnish, Deliver and Install Signage

Bid Open Location: DASNY, Corporate Headquarters, 515 Broadway, Albany, NY 12207 Bid Open Date and Time: December 22, 2022 at 2:30 p.m.

Item	Sign	Description/Location	Qty	UOM	Unit	Extended
No.	Туре				Cost	Price
1	C1	Floor ID /Elevator Egress	13	EA	\$	\$
2	C1A	Elevator Egress	14	EA	\$	\$
3	C2	Building Directory	23	EA	\$	\$
4	C3	Floor Directory	15	EA	\$	\$
5	L1	Emergency Information	3	EA	\$	\$
6	L2A	Maximum Occupancy	4	EA	\$	\$
7	L2B	Electronic Surveillance	37	EA	\$	\$
8	L3A	Small Regulatory	33	EA	\$	\$
9	L3B	Medium Regulatory/No Smoking	56	EA	\$	\$
10	L3C	Smoke Free Campus	6	EA	\$	\$
11	L4	Fire Regulatory	0	EA	\$	\$
12	L5	Large Regulatory	6	EA	\$	\$
13	L6	Fire Regulatory/No Storage	16	EA	\$	\$
		Permitted				
14	L7	Elevator Machine Room	1	EA	\$	\$
15	R1	Room ID	125	EA	\$	\$
16	R2	Conference Room ID	13	EA	\$	\$
17	R3	Office ID	300	EA	\$	\$
18	R4	Classroom ID	44	EA	\$	\$
19	R5	Restroom ID	29	EA	\$	\$
20	R5A	All Gender Restroom ID	13	EA	\$	\$
21	R6	Utility / Storage ID	173	EA	\$	\$
22	R7	Locker Room ID	4	EA	\$	\$
23	R8	All Gender Locker ID	2	EA	\$	\$
24	R9	Locker ID	8	EA	\$	\$
25	S8	Emergency Exit Door Band	2	EA	\$	\$
26	W4	Floor Directional	20	EA	\$	\$
27	W5	Corridor Directional	28	EA	\$	\$
28	W8A	Department / Room ID @ double	12	EA	\$	\$

BIDDING REQUIREMENTS for PURCHASING

		doors			
29	W8B	Department / Room ID @ single	14	EA	\$ \$
		door			
30	W8C	Department / Room ID @ Glass	14	EA	\$ \$
		Transom			
31	W8D	Department / Room ID @ single	2	EA	\$ \$
		door 10" H			
32	W8E	Department / Room ID @ single	3	EA	\$ \$
		door 14" H			
33	W9A	Overhead Directional - Wall	3	EA	\$ \$
		Mounted			
34	W9B	Overhead Directional - Left @ Glass	5	EA	\$ \$
		Transom			
35	W9C	Overhead Directional - Right @	4	EA	\$ \$
		Glass Transom			
36	W10	Restroom Flag	34	EA	\$ \$
37	W11	Department / Directional Flag	35	EA	\$ \$
38	W12	Recycling Flag	22	EA	\$ \$
39	W13	Locker / Fitness ID	2	EA	\$ \$
40	NA	Removal of Existing Signage		LS	\$ \$
41	NA	Installation of Signage		LS	\$ \$
42	NA	Bonds		LS	\$ \$

NOTICE AND INFORMATION FOR BIDDERS

See below for specific Signage Dimensions and Materials & Construction.

INSTALLATION LABOR (if required) LABOR TO INSTALL

Estimated No. of Hours ______ Hourly Rate (*Prevailing Wage rates are required for this work*)______

TOTAL BID_____

BIDDING REQUIREMENTS for PURCHASING

NOTICE AND INFORMATION FOR BIDDERS

(The below questions 1) and 2) need only be answered if the above total bid is for one million dollars or more)

- 1. Does your firm anticipate the use of subcontractors and outside suppliers specific to this procurement Yes No
- 2. Does your firm anticipate the creation of employment opportunities arising from this procurement? Yes No

(The below information must be completed for all bids.) Identify all subcontractors, if any:

STATE, PROVINCE FOR FOREIGN COUNTRY THAT YOUR FIRM'S PRINCIPAL PLACE OF	
BUSINESS IS LOCATED:	BIDDER (FIRM NAME)
ADDRESS OF FACTORY OR PLANT WHERE ITEMS ARE MANUFACTURED AND/OR ASSEMBLED. (Attach additional sheet(s) if more	SIGNATURE
than one manufacturer)	NAME (TYPE/PRINTED)
	TITLE

Date



Attachment B: Detailed Specifications and Scope of Work

Furnish, deliver and install new interior signage and removal of existing signage at John Jay College of Criminal Justice – Haaren Hall per the DASNY Signage Specifications and Removal scope.

Detailed Specifications:

Prepared by TSquared Design dated 10/18/2022

Scope of Work:

Bidder is responsible for furnishing, delivering and installing new signage per the specifications included in this Bid. Low Bidder is required to provide samples, conduct field verification and provide shop drawings prior to production of signs and installation services.

Bidder is also responsible for removing and disposing of all the existing signage shown in Haaren Hall Building Signage Removals as per Existing Signage Audit prepared by TSquared Design dated 11/17/2022.

Any and all existing areas that are damaged by signage removals or new signage installations shall be patched as required to match existing adjacent area in material, finish and color, as follows:

Corridor walls: White dove 06 – Eggshell finish Corridors on 2nd floor: White dove 06 – Semi gloss finish

Bidder must promptly install new signage as soon as the existing signage is removed, and patching is complete.

See Issued for Bid_2022_1018 drawing set for further details and locations.

Item No.	Sign Type	Description/Location	Dimensions (W x H x TH)	Materials & Construction	Quantity
	Wayfindi	ng Signage			
1	C1	Floor ID / Elevator Egress	22" W x 50-7/16" H x 1/8" TH	1/8" horizontal satin aluminum floor number panel with engraved & filled two color egress map	13
2	C1A	Elevator Egress	12" W x 10" H x 1/8" TH	1/8" horizontal satin aluminum engraved & filled two color egress map	14
3	C2	Building Directory	22" W x 50-7/16" H	APCO "Elevate" w/ 1/16" reveal between slats Satin anodized aluminum sign bands	23
4	C3	Floor Directory	27" W x 94" H x 1/8" TH	1/8" acrylic panel, reverse print graphics.1/4" TH dimensional number, painted face and returns - 2 colors	15
5	L1	Emergency Information	12" W x 16" H x 1/8" TH	1/8" horizontal satin aluminum, engraved copy, direct print logo	3
6	L2A	Maximum Occupancy	12" W x 16" H x 1/8" TH	1/8" horizontal satin aluminum, engraved copy, direct print logo	4
7	L2B	Electronic Surveillance	10" W x 7-3/4" H x 1/8" TH	1/8" horizontal satin aluminum, engraved copy, direct print logo	37
8	L3A	Small Regulatory	8" W x 4" H x 1/8" TH	1/8" horizontal satin aluminum, engraved copy	33
9	L3B	Medium Regulatory/ No Smoking	8" W x 6" H x 1/8" TH	1/8" horizontal satin aluminum, engraved copy	56
10	L3C	Smoke Free Campus	9-5/8" W x 13" H x 1/8" TH	1/8" horizontal satin aluminum, engraved copy, direct print logo	6
11	L4	Fire Regulatory	6" W x 6-1/2" H x 1/4" D	1/4" TH. Painted Acrylic Silkscreen Text	0
12	L5	Large Regulatory	10-1/2" W x 8" H x 1/4" D	1/4" TH. Painted Acrylic - 2 colors Silkscreen Text	6
13	L6	Fire Regulatory/ No Storage Permitted	10-1/2" W x 8" H x 1/4" D	1/4" TH. Painted Acrylic Silkscreen Text	16
14	L7	Elevator Machine Room	2" CH	Die-cut Vinyl Letters (19 letters)	1
15	R1	Room ID	8-1/2" W x 8-1/2" H	APCO "Fullview" Series Natural Satin Anodized Header DPT (Direct Print Tactile) Graphics Insert: Laser printed graphics	125
16	R2	Conference Room ID	8-1/2" W x 9-3/4" H	APCO "Fullview" Series Natural Satin Anodized Header DPT (Direct Print Tactile) Graphics Insert: Laser printed graphics APCO Signband Notifier Message Strip - Natural Satin Anodized	13
17	R3	Office ID	5-1/8" W x 6-3/16" H APCO "Fullview" Series Natural Satin Anodized Header DPT (Direct Print Tactile) Graphics Insert: Laser printed graphics APCO Signband Notifier Message Strip - Na Satin Anodized		300
18	R4	Classroom ID	5" W x 5-7/16" H x 1/4" TH	1/4" horizontal satin aluminum, Tactile Copy, Grade II Braille APCO Signband Notifier Message Strip - Natural Satin Anodized	44
19	R5	Restroom ID	Tactile panel: 6" W x 7-3/4" H x 1/4" TH Non-tactile panel: 6" W x 3" H x 1/4" TH	Tactile Panel: 1/4" P-95 acrylic, back-painted white DPT (Direct Print Tactile and Braille) Graphics Non-Tactile Panel: 1/4" P-95 acrylic, back-painted white Silkscreened Text	29

Item No.	Sign Type	Description/Location	Dimensions (W x H x TH)	Materials & Construction	Quantity
20	R5A	All Gender Restroom ID	Tactile panel: 6" W x 8-3/4" H x 1/4" TH Non-tactile panel: 6" W x 3" H x 1/4" TH	Tactile Panel: 1/4" P-95 acrylic, back-painted white DPT (Direct Print Tactile and Braille) Graphics Non-Tactile Panel: 1/4" P-95 acrylic, back-painted white Silkscreened Text	13
21	R6	Utility / Storage ID	6" W x 6" H x 1/4" TH	1/4" P-95 acrylic, back-painted white DPT (Direct Print Tactile and Braille) Graphics	173
22	R7	Locker Room ID	Tactile panel: 8-1/2" W x 8-1/2" H Non-tactile panel: 8-1/2" W x 3" H x 1/4" TH	Tactile panel: APCO "Fullview" Series Natural Satin Anodized Header DPT (Direct Print Tactile) Graphics Insert: DPT Icon on acrylic Non-Tactile Panel: P-95 acrylic, back-painted white Silkscreened Text	4
23	R8	All Gender Locker ID	Tactile panel: 6" W x 8-3/4" H x 1/4" TH Non-tactile panel: 6" W x 3" H x 1/4" TH	Tactile panel: 1/4" P-95 acrylic, back-painted white DPT (Direct Print Tactile and Braille) Graphics Non-Tactile Panel: 1/4" P-95 acrylic, back-painted white Silkscreened Text	2
24	R9	Locker ID	Tactile panel: 6" W x 8-3/4" H x 1/4" TH Non-tactile panel: 6" W x 3" H x 1/4" TH	Tactile panel: 1/4" P-95 acrylic, back-painted white DPT (Direct Print Tactile and Braille) Graphics Non-Tactile Panel: 1/4" P-95 acrylic, back-painted white Silkscreened Text	8
25	S8	Emergency Exit Door Band	28-1/2" (VIF) W x 3-1/4" H x 1/8" TH	1/8" TH. Painted Acrylic Silkscreen Text	2
26	W4	Floor Directional	22" W x 28" H	APCO "Full View" Changeable Sign w/ Natural Aluminum Frame, components and background panel. Digitally printed paper insert	20
27	W5	Corridor Directional	10" W x 10" H	APCO "Full View" Changeable Sign w/ Natural Aluminum Frame, components and background panel. Digitally printed paper insert	28
28	W8A	Department / Room ID @ double doors	Width varies (approx. 76" W) x 12" H	End Panels: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow Department Name Panel: 1/4" TH. P-95 acrylic, back-painted white 1/4" TH. painted acrylic Letters Panels mount to a 1/16" TH. common back plate. Department Name Panel mounts to common back plate w/ 3M Dual Lock to allow changeability Field Verify All Locations	12
29	W8B	Department / Room ID @ single door	Width varies (approx. 40" W) x 12" H	End Panels: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow Department Name Panel: 1/4" TH. P-95 acrylic, back-painted white 1/4" TH. p-95 acrylic Letters Panels mount to a 1/16" TH. common back plate. Department Name Panel mounts to common back plate w/ 3M Dual Lock to allow changeability Field Verify All Locations	14


Item No.	Sign Type	Description/Location	Dimensions (W x H x TH)	Materials & Construction	Quantity
				End Panels: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow	
	W8C	Department / Room ID @ Glass Transom	Width varies (approx. 71" W) x 12" H	Department Name Panel: 1/4" TH. P-95 acrylic, back-painted white 1/4" TH. painted acrylic Letters	14
				Panels mount to a 1/16" TH. common back plate. Department Name Panel mounts to common back plate w/ 3M Dual Lock to allow changeability	
30				Field Verify All Locations	
				End Panels: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow	
	W8D	Department / Room ID @ single door	Width varies (approx. 40" W) x 10" H	Department Name Panel: 1/4" TH. P-95 acrylic, back-painted white 1/4" TH. painted acrylic Letters	2
		10" H		Panels mount to a 1/16" TH. common back plate. Department Name Panel mounts to common back plate w/ 3M Dual Lock to allow changeability	
31				Field Verify All Locations	
				End Panels: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow	
	W8E	Department / Room ID @ single door	Width varies (approx. 40" W) x 14" H	Department Name Panel: 1/4" TH. P-95 acrylic, back-painted white 1/4" TH. painted acrylic Letters	3
		14" H		Panels mount to a 1/16" TH. common back plate. Department Name Panel mounts to common back plate w/ 3M Dual Lock to allow changeability	
32				Field Verify All Locations	
				End Panels: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow	
	W9A	Overhead Directional - Wall Mounted	Width varies (approx. 76" W) x 12" H	Department Name Panel: 1/4" TH. P-95 acrylic, back-painted white 1/4" TH. painted acrylic Letters	3
				Panels mount to a 1/16" TH. common back plate. Department Name Panel mounts to common back plate w/ 3M Dual Lock to allow changeability	
33				Field Verify All Locations	
		Our dia set Directions l		End Panel: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow	
	W9B		Width varies (approx. 71" W) x 12" H	Department Name Panel: 1/4" TH. painted acrylic Letters applied on 3M "Dusted Crystal" Vinyl	5
34				Field Verify All Locations	
				End Panel: 1/4 TH. horizontal satin aluminum w/ 1/4" TH. painted acrylic number/arrow	
	W9C	Overhead Directional - Right @ Glass Transom	Width varies (approx. 71" W) x 12" H	Department Name Panel: 1/4" TH. painted acrylic Letters applied on 3M "Dusted Crystal" Vinyl	4
35				Field Verify All Locations	
36	W10	Restroom Flag	14" W x 10" H x 3/4" TH	(Two-sided Sign) P-95 acrylic, back-painted white Direct Digital Print Symbol	34
37	W11	Department / Directional Flag	12" W x 8-1/2" H x 3/4" TH	(Two-sided Sign) P-95 acrylic, back-painted white Direct Digital Print Symbol	35

Item No.	Sign Type	Description/Location	Dimensions (W x H x TH)	Materials & Construction	Quantity
38	W12	Recycling Flag	8-1/2" W X 8-1/2" H X 3/4" TH	(Two-sided Sign) P-95 acrylic, back-painted white Direct Digital Print Symbol	22
39	W13	Locker / Fitness ID	15-7/8" CH.	1/4" TH. Laser-cut Acrylic Letters - 7 Letters Face and returns painted	2

T-SQUARED DESIGN, INC



Attachment C: Site Logistics



HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE

INTERIOR SIGNAGE & WAYFINDING ISSUED FOR BID

OCTOBER 18, 2022



QUALIFICATIONS

Sign Fabricator: A Signage Fabricator who is able to prove demonstrated capability with a complete project record satisfactory to the Owner and who is able to prepare shop drawings and samples, and to manufacture, fabricate, assemble and install the work shown in these drawings.

Responsibility: The Fabricator shall assume responsibility for the quality of materials and workmanship required for the execution of the work shown herein. The Fabricator shall guarantee all materials and workmanship for a period of (3) year following the final acceptance of the work. During this period, if defects or faulty materials are found, the Fabricator shall proceed immediately upon notification by the owner to remedy the condition at his own expense, together with any damage to surrounding finishes or furnishings which occurred as a result of those defects.

Submittals: The Fabricator shall submit to Architect and Signage Consultant for approval, samples of finish, color swatches and final sign samples as required. Sample submittal and approval shall be for color, texture, and graphic image only. Compliance with all other requirements is the exclusive responsibility of the Fabricator.

The Fabricator shall submit full scale samples signs using actual materials as specified for the signs indicated. Samples shall be submitted to Signage Consultant and Architect for approval within 5 working days of receiving authorization to proceed.

The Fabricator shall furnish information and coordinate with related trades to assure satisfactory completion of the work, In all cases, where installation of mounting hardware involves other trades, coordination shall be through the Construction Manager. All installers will be of the appropriate unions to assure labor harmony.

Complete shop drawings shall be prepared by the Fabricator for all sign types calling out, in detail, specifications and dimensions including all message schedules and full size sections of typical sign types, if required. Fabricator shall submit shop drawing set to the Architect and Signage Consultant for approval before fabrications start.

The Signage Consultant will review up to 2 rounds of shop drawings. Additional rounds will be considered additional scope and billed accordingly.

Variations in quantities as determined by the Fabricator compared with the message schedule shall be reported to the Signage Consultant and Architect prior to submission of bid.

The Fabricator shall verify all measurements and take all field measurements necessary before fabrication. The Fabricator shall provide all materials and parts necessary to complete each sign type, even though such work is not definitely shown or specified. The Fabricator shall provide all bolts, and anchors, support, braces, connections, and other items necessary for completion of the work. The Fabricator shall form signs to shape and size with clean, clear, sharp lines and angles. Drilled holes for bolt or screw fasteners shall have clean, true lines and surfaces.

Exposed surfaces of work shall have a smooth finish, free of blemishes. Where tight fit is required, joints are to be made to a close fit. Work shall be accurately set to established lines and elevations and securely fastened into place. Work shall be executed and finished in accordance with approved drawings, cuts, details, and samples. Visible screw heads and fasteners shall occur only at locations indicated on the drawings and approved submittals. All edges and corners of finished letter forms and graphics are to be true and clean.

GRAPHIC APPLICATION

Artwork: The Fabricator shall furnish all typography and all necessary artwork for reproduction, based on our Issued for Construction submission, except where noted or otherwise specified. The Final shop drawing submittals from the Fabricator to the Signage Consultant and Architect, which shows all layouts will be the proofs of actual copy layout approval prior to fabrication showing properly kerned copy.

All letter forms shall be aligned to maintain a base line parallel to the sign format. The typeface shall conform with sections including Colors and Typeface Section of our Issued for Construction submission set. Alternate type will not be accepted.

Letter and word spacing shall be optical but in conformance with the examples shown on the drawings.

Complete alphabets, numbers, punctuation and symbols shall be submitted to Signage Consultant / Architect for approval prior to any fabrication.

All letters, regardless of material or process, shall be executed in such a manner that all edges and corners of finished letterforms are true and clean. Letterforms with rounded positive and negative corners, edge build-up or bleeding will not be accepted.

ADA: Unless noted otherwise, all signs, where applicable, shall comply with ADA guidelines in respect to type size, tactile lettering, braille usage (grade II), and mounting heights.

Walk-Through: The Fabricator shall arrange a meeting with the Sign Consultant and Architect at the site for the final location and alignment of sign elements. Installation: The signs shall be installed at typical locations as specified in the respective drawings, at mounting heights indicated and by methods shown or specified.

Protection: The Fabricator shall protect the work and adjacent work and materials from damage during progress of the work until completion. Finished work shall be wrapped with paper, polyethylene film, or stripable waterproof tape for shipment and storage and protection for damage during installation.

Adjust and Clean: The Fabricator shall repair any damage incurred during installation to the satisfaction of the Sign Consultant / Architect. Signs which cannot be repaired to a new condition must be replaced. All sign surfaces must be clean, free of smudging and fingerprinting. All hardware and electrical equipment are to be adjusted to assure safe and proper operation and installation. All waste and debris shall be discarded. The Fabricator shall arrange with the General Contractor for the use of waste receptacle.

Message Schedule and Location Plans

Message Schedule: Room Numbering, Sign Number, Copy, and Quantity and any pertinent remarks are listed in the message schedule.

Copy and Graphics: The sign schedule shall indicate only the copy for each sign. Format for all copy shall be as specified on the drawing sheet for each sign.

Location Plans: Each sign shall be located typically as indicated on the sign drawing sheet. Conditions that may exist which prevent location of signage as specified shall be brought to the Sign Consultant and Architect's attention prior to installation.

PRICING

Bid Breakdown: The Fabricator shall provide unit prices for each sign type and extended costs for the total quantity of each sign type. The cost of installation shall be a separate lump sum for the entire project.

Unit Price Guarantee: The Fabricator shall provide unit price guarantees for the duration of the project. The Fabricator shall guarantee bid prices for 90 days. The Fabricator shall also provide a unit price schedule to the owner that will be guaranteed for a period of (1) year after completion of the job. Installation charges should be included as a separate item in the schedule.

over scaled dimensions.

Inspection: The Fabricator shall inspect condition of locations and surfaces where signs are to be installed. The Fabricator shall not proceed with installation until defects or errors which would result in poor installation have been corrected.

APCO New York Veronica Crothers, Account Manager (914) 793-0483 vcrothers@apcosigns.com

PROTOTYPES FROM SELECTED VENDORS

Vendors selected as finalists for this bid will be required to provide samples of the following sign types for final approval:

C1 - Floor ID with Elevator Egress C3 - Floor Directory L3C - Smoke Free Campus Sign L4 - Fire Regulatory Sign R4 - Classroom ID R5 - Restroom ID R6 - Utility/Storage ID W8B - Dept. Room ID @ Single Door

NOTE: Material finishes and color swatch samples to be provided for approval



Fabrication and Manufacture

Verification: The Fabricator shall verify and be responsible for all dimensions and conditions shown on these drawings. Written dimensions shall take precedence

The Sign Consultant and Architect shall be notified of any discrepancies in the drawings and/or graphic schedule, in field dimensions or conditions, and/or changes required in construction details.

Design Intent: The drawings were issued to show design intent, not actual fabrication. The Fabricator will submit fully detailed shop drawings for written acceptance by Signage Consultant and Architect prior to fabrication. The fabricator will provide any engineered stamped shop drawings as required. It is the responsibility of the Fabricator to bring any discrepancies in these drawings to the attention of the Signage Consultant prior to fabrication.

Field verification required on all wall surfaces called out in the drawing for graphics or signage. A full site visit to review all conditions is required.

Manufacter System: Apco Graphics, Inc. (no substitutes allowed)

SIGN TYPES AND QUANTITIES

JOHN JAY C	OLLEGE - HAAREN HALL	INTERIOR	SIGNAGE							TOTALS
SIGN TYPE	DESCRIPTION	Cellar	Floor L	Floor 1	Floor 2	Floor 3	Floor 4	Floor 5	Floor 6	
C1	Floor ID w/ Elevator Egress	1	2	0	2	2	2	2	2	13
C1A	Elevator Egress	1	3	5	1	1	1	1	1	14
C2	Building Directory	1	2	0	4	4	4	4	4	23
C3	Floor Directory	1	2	2	2	2	2	2	2	15
L1	Emergency Information	0	0	0	0	1	0	0	2	3
L2A	Maximum Occupancy	0	1	0	0	1	1	0	1	4
L2B	Electronic Surveillance	2	6	6	5	4	4	7	3	37
L3A	Small Regulatory	2	10	2	2	3	2	3	10	34
L3B	Medium Regulatory/No Smoking	9	6	6	9	10	2	6	7	55
L3C	Smoke Free Campus	0	0	2	0	0	1	0	3	6
L4	Fire Regulatory	0	0	0	0	0	0	0	0	0
L5	Large Regulatory	6	0	0	0	0	0	0	0	6
L6	Fire Regulatory/No Storage Permitted	3	3	2	1	1	2	2	2	16
L7	Elevator Machine Room	0	1	0	0	0	0	0	0	1
R1	Room ID	18	20	12	11	12	18	15	19	125
R2	Conference Room ID	0	0	1	0	1	1	3	7	13
R3	Office ID	5	13	14	1	44	82	84	57	300
R4	Classroom ID	0	0	1	27	9	2	3	2	44
R5	Restroom	2	5	2	5	5	2	4	4	29
R5A	All Gender Restroom	6	1	2	1	0	0	2	1	13
R6	Utility/Storage Room ID	19	25	8	15	41	16	18	31	173
R7	Locker Room ID	0	0	0	0	4	0	0	0	4
R8	All Gender Locker Room ID	0	0	0	0	2	0	0	0	2
R9	Locker ID	0	0	0	0	8	0	0	0	8
S8	Emergency Exit Door Band	0	2	0	0	0	0	0	0	2
W4	Floor Directional	0	0	0	4	4	4	4	4	20
W5	Corridor Directional	5	1	7	8	2	1	2	2	28
W8A	Dept/Room ID @ double doors	1	1	0	1	2	1	2 2	4	12
W8B	Dept/Room ID @ single door	0	0	0	3	2	4		3	14
W8C	Dept/Room ID @ glass transom	0	0	0	1	2	5	3	3	14
W8D	Dept/Room ID @ single door - 10" H	0	0	0	0	0	0	0 0	2	2
W8E	Dept/Room ID @ single door - 14"H	0	0	0	0	0	2		1	5
W9A	Overhead Directional - wall mounted	0	0	0	2	0	0	1	0	3
W9B	Overhead Directional - left @ glass transom	0	0	0	0	1	2	1	1	5
W9C	Overhead Directional - right @ glass transom	0	0	0	0	1	2	1	0	4
W10 W11	Restroom Flag	2 0	7 0	3 0	6 0	5 8	2 7	5 13	4 7	34
W11 W12	Dept/Directional Flag Recycling Flag	1	0		8	8		2		35 22
				1			4		1	
W13	Locker/Fitness ID	0	0	0	0	2	0	0	0	2





TYPOGRAPHY AND COLORS

HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE

SIGNAGE & WAYFINDING | ISSUED FOR BID



T-SQUARED DESIGN | 10.18.2022 | 4

NIMBUS SANS NOVAS MEDIUM CONDENSED	NIMBUS SANS NOVAS BOLD CONDENSED
ABCDEFGHI	ABCDEFGHI
JKLMNOPQR	JKLMNOPQR
STUVWXYZ	STUVWXYZ
abcdefghi	abcdefghi
jklmnopqr	jklmnopqr
stuvwxyz	stuvwxyz
1234567890	1 2 3 4 5 6 7 8 9 0

ABCDEFGHI
JKLMNOPQR
STUVWXYZ
abcdefghi
jklmnopqr
stuvwxyz
1 2 3 4 5 6 7 8 9 0

NIMBUS SANS NOVAS HEAVY CONDENSED

A B C D E F G H I JKLMNOPQR S T U V W X Y Z abcdefghi jklmnopqr stuvwxyz 1 2 3 4 5 6 7 8 9 0

MAIN COLORS





SIGN FAMILY

HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE

SIGNAGE & WAYFINDING | ISSUED FOR BID



T-SQUARED DESIGN | 10.18.2022 | 6


SIGN FAMILY - WAYFINDING



W4 WALL DIRECTIONAL

410 Office of Student Academic Engagement & Retention

W8A DEPT/ROOM ID (WALL MOUNTED @ DOUBLE DOORS)



W8B DEPT/ROOM ID (WALL MOUNTED @ SINGLE DOOR)


W8B DEPT/ROOM ID (WALL MOUNTED @ SINGLE DOOR) - ALT LAYOUT

↑ 4.22.16 - 4.22.22 ← 4.22.24 - 4.22.27

W5 CORRIDOR DIRECTIONAL

422 Department of Law, Police Science and Criminal Justice Administration

W8C DEPT/ROOM ID (@ GLASS TRANSOM)



W8D WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR)




Security, Fire & Emergency Management

Faculty Services, Marketing & Communications and Public Affairs

W8E WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR)


SCALE 1-1/2" = 1'-0"



W9A OVERHEAD DIRECTIONAL ON WALL



W9B OVERHEAD DIRECTIONAL ON GLASS TRANSOM (LEFT)



W9C OVERHEAD DIRECTIONAL ON GLASS TRANSOM (RIGHT)



JOHN JAY COLLEGE OF CHIMINAL USTICE



W10 RESTROOM FLAG



W11 FLAG (ROOM ID)



- - - -

SCALE 1-1/2" = 1'-0"

SIGN FAMILY - WAYFINDING



SCALE 1-1/2" = 1'-0"

C3 FLOOR DIRECTORY

SCALE 1" = 1'-0"



	Γ

Gymnasium

400

410

421

422

431

432 SEEK

433

Office of Student Academic Engagement & Retention

420 Athletics Annex

Athletics


Law, Police Science and Criminal Justice Administration

Conference Room

Security, Fire and Emergency Management

436/438/439 SEEK Tutoring Labs

ROOM IDENTIFICATION AND LIFE SAFETY



EMERGENCY EXIT ONLY ALARM WILL SOUND

S8 EMERGENCY EXIT DOOR BAND USE NO WATER

L4 FIRE REGULATORY NO STORAGE PERMITTED

ONLY

L5 LARGE REGULATORY

L6 NO STORAGE

SCALE 1-1/2" = 1'-0"



THIS CAMPUS **IS PROTECTED BY ELECTRONIC** SURVEILLANCE

JOHN

L2B ELECTRONIC SURVEILLANCE



THIS IS A TOBACCO FREE CAMPUS. SMOKING OR USE OF E-CIGARETTES IS NOT PERMITTED ANYWHERE ON CAMPUS. JOHN JAY

L3C SMOKE FREE CAMPUS



ELEVATOR MACHINE ROOM

L7 ELEVATOR MACHINE ROOM

SIGN LOCATION PLANS

HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE


SIGNAGE & WAYFINDING | ISSUED FOR BID - ADDENDUM 1






T-SQUARED DESIGN | 10.18.2022 | 11

SIGN LOCATION PLAN - CELLAR WAYFINDING AND LIFE SAFETY






SIGN SYMBOL	SIGN TYPE	DESCRIPTION
STIVIDOL	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	FLEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	
	L2B	ELECTRONIC SURVEILLANCE
	L3A	
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	 L5	LARGE REGULATORY
	_0 L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	 R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATI	ON LEGEND	





SIGN LOCATION PLAN - CELLAR ROOM IDENTIFICATION




JOHN JAY COLLEGE OF CRIMINAL JUSTICE

SIGN SYMBOL	SIGN TYPE	DESCRIPTION
STIVIDOL	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	FLEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	
	L2B	ELECTRONIC SURVEILLANCE
	L3A	
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	 L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	 R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATI	ON LEGEND	






SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATI	ION LEGEND	





SIGN LOCATION PLAN - FLOOR L ROOM IDENTIFICATION







SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATION LEGEND		






SIGN SYMBOL	SIGN TYPE	DESCRIPTION	
	C1	FLOOR ID W/ELEVATOR EGRESS	
	C1A	ELEVATOR EGRESS	
	C2	BUILDING DIRECTORY	
	C3	FLOOR DIRECTORY	
	L1	EMERGENCY INFORMATION	
	L2A	MAXIMUM OCCUPANCY	
	L2B	ELECTRONIC SURVEILLANCE	
	L3A	SMALL REGULATORY	
	L3B	MED REGULATORY/NO SMOKING	
	L3C	SMOKE FREE CAMPUS	
	L4	FIRE REGULATORY	
	L5	LARGE REGULATORY	
	L6	FIRE REGULATORY/NO STORAGE PERMITTED	
	L7	ELEVATOR MACHINE ROOM	
	R1	ROOM ID	
	R2	CONFERENCE ROOM ID	
	R3	OFFICE ID	
	R4	CLASSROOM ID	
	R5	RESTROOM	
	R5A	ALL GENDER RESTROOM	
	R6	UTILITY/STORAGE ROOM ID	
	R7	LOCKER ROOM ID	
	R8	ALL GENDER LOCKER ROOM ID	
	R9	LOCKER ID	
	S8	EMERGENCY EXIT DOOR BAND	
	W4	FLOOR DIRECTIONAL	
	W5	CORRIDOR DIRECTIONAL	
	W8A	DEPT/ROOM ID @ DOUBLE DOORS	
	W8B	DEPT/ROOM ID @ SINGLE DOORS	
	W8C	DEPT/ROOM ID @ GLASS TRANSOM	
	W8D	DEPT/ROOM ID @ SINGLE DOOR	
	W8E	DEPT/ROOM ID @ SINGLE DOOR	
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED	
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM	
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM	
	W10	RESTROOM FLAG	
	W11	DEPT/DIRECTIONAL FLAG	
	W12	RECYCLING FLAG	
	W13	AREA IDENTIFICATION	
SIGN LOCAT	SIGN LOCATION LEGEND		










SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATI	ION LEGEN	D






SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATI	ON LEGEND	






SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATI	ON LEGENI)




SIGN LOCATION PLAN - FLOOR 3 WAYFINDING AND LIFE SAFETY






SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATI	ION LEGEND	




SIGN LOCATION PLAN - FLOOR 3 ROOM IDENTIFICATION







SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
		RECYCLING FLAG
	W13	AREA IDENTIFICATION

SIGN LOCATION LEGEND






SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATION LEGEND		




SIGN LOCATION PLAN - FLOOR 4 ROOM IDENTIFICATION



SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
		RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATION LEGEND		




SIGN LOCATION PLAN - FLOOR 5 WAYFINDING AND LIFE SAFETY





SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION
SIGN LOCATIO	ON LEGEND	




SIGN LOCATION PLAN - FLOOR 5 ROOM IDENTIFICATION






SIGN SYMBOL	SIGN TYPE	DESCRIPTION
	C1	FLOOR ID W/ELEVATOR EGRESS
	C1A	ELEVATOR EGRESS
	C2	BUILDING DIRECTORY
	C3	FLOOR DIRECTORY
	L1	EMERGENCY INFORMATION
	L2A	MAXIMUM OCCUPANCY
	L2B	ELECTRONIC SURVEILLANCE
	L3A	SMALL REGULATORY
	L3B	MED REGULATORY/NO SMOKING
	L3C	SMOKE FREE CAMPUS
	L4	FIRE REGULATORY
	L5	LARGE REGULATORY
	L6	FIRE REGULATORY/NO STORAGE PERMITTED
	L7	ELEVATOR MACHINE ROOM
	R1	ROOM ID
	R2	CONFERENCE ROOM ID
	R3	OFFICE ID
	R4	CLASSROOM ID
	R5	RESTROOM
	R5A	ALL GENDER RESTROOM
	R6	UTILITY/STORAGE ROOM ID
	R7	LOCKER ROOM ID
	R8	ALL GENDER LOCKER ROOM ID
	R9	LOCKER ID
	S8	EMERGENCY EXIT DOOR BAND
	W4	FLOOR DIRECTIONAL
	W5	CORRIDOR DIRECTIONAL
	W8A	DEPT/ROOM ID @ DOUBLE DOORS
	W8B	DEPT/ROOM ID @ SINGLE DOORS
	W8C	DEPT/ROOM ID @ GLASS TRANSOM
	W8D	DEPT/ROOM ID @ SINGLE DOOR
	W8E	DEPT/ROOM ID @ SINGLE DOOR
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM
	W10	RESTROOM FLAG
	W11	DEPT/DIRECTIONAL FLAG
	W12	RECYCLING FLAG
	W13	AREA IDENTIFICATION

SIGN LOCATION LEGEND




SIGN LOCATION PLAN - FLOOR 6 WAYFINDING AND LIFE SAFETY




JOHN JAY COLLEGE OF SUBSTICE

SIGN SYMBOL	SIGN TYPE	DESCRIPTION		
	C1	FLOOR ID W/ELEVATOR EGRESS		
	C1A	ELEVATOR EGRESS		
	C2	BUILDING DIRECTORY		
	C3	FLOOR DIRECTORY		
	L1	EMERGENCY INFORMATION		
	L2A	MAXIMUM OCCUPANCY		
	L2B	ELECTRONIC SURVEILLANCE		
	L3A	SMALL REGULATORY		
	L3B	MED REGULATORY/NO SMOKING		
	L3C	SMOKE FREE CAMPUS		
	L4	FIRE REGULATORY		
	L5	LARGE REGULATORY		
	L6	FIRE REGULATORY/NO STORAGE PERMITTED		
	L7	ELEVATOR MACHINE ROOM		
	R1	ROOM ID		
	R2	CONFERENCE ROOM ID		
	R3	OFFICE ID		
	R4	CLASSROOM ID		
	R5	RESTROOM		
	R5A	ALL GENDER RESTROOM		
	R6	UTILITY/STORAGE ROOM ID		
	R7	LOCKER ROOM ID		
	R8	ALL GENDER LOCKER ROOM ID		
	R9	LOCKER ID		
	S8	EMERGENCY EXIT DOOR BAND		
	W4	FLOOR DIRECTIONAL		
	W5	CORRIDOR DIRECTIONAL		
	W8A	DEPT/ROOM ID @ DOUBLE DOORS		
	W8B	DEPT/ROOM ID @ SINGLE DOORS		
	W8C	DEPT/ROOM ID @ GLASS TRANSOM		
	W8D	DEPT/ROOM ID @ SINGLE DOOR		
	W8E	DEPT/ROOM ID @ SINGLE DOOR		
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED		
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM		
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM		
	W10	RESTROOM FLAG		
	W11	DEPT/DIRECTIONAL FLAG		
	W12	RECYCLING FLAG		
	W13	AREA IDENTIFICATION		
SIGN LOCATION LEGEND				




SIGN LOCATION PLAN - FLOOR 6 ROOM IDENTIFICATION



SIGN SYMBOL	SIGN TYPE	DESCRIPTION		
	C1	FLOOR ID W/ELEVATOR EGRESS		
	C1A	ELEVATOR EGRESS		
	C2	BUILDING DIRECTORY		
	C3	FLOOR DIRECTORY		
	L1	EMERGENCY INFORMATION		
	L2A	MAXIMUM OCCUPANCY		
	L2B	ELECTRONIC SURVEILLANCE		
	L3A	SMALL REGULATORY		
	L3B	MED REGULATORY/NO SMOKING		
	L3C	SMOKE FREE CAMPUS		
	L4	FIRE REGULATORY		
	L5	LARGE REGULATORY		
	L6	FIRE REGULATORY/NO STORAGE PERMITTED		
	L7	ELEVATOR MACHINE ROOM		
	R1	ROOM ID		
	R2	CONFERENCE ROOM ID		
	R3	OFFICE ID		
	R4	CLASSROOM ID		
	R5	RESTROOM		
	R5A	ALL GENDER RESTROOM		
	R6	UTILITY/STORAGE ROOM ID		
	R7	LOCKER ROOM ID		
	R8	ALL GENDER LOCKER ROOM ID		
	R9	LOCKER ID		
	S8	EMERGENCY EXIT DOOR BAND		
	W4	FLOOR DIRECTIONAL		
	W5	CORRIDOR DIRECTIONAL		
	W8A	DEPT/ROOM ID @ DOUBLE DOORS		
	W8B	DEPT/ROOM ID @ SINGLE DOORS		
	W8C	DEPT/ROOM ID @ GLASS TRANSOM		
	W8D	DEPT/ROOM ID @ SINGLE DOOR		
	W8E	DEPT/ROOM ID @ SINGLE DOOR		
	W9A	OVERHEAD DIRECTIONAL - WALL MOUNTED		
	W9B	OVERHEAD DIRECTIONAL @ GLASS TRANSOM		
	W9C	OVERHEAD DIRECTIONAL @ GLASS TRANSOM		
	W10	RESTROOM FLAG		
	W11	DEPT/DIRECTIONAL FLAG		
	W12	RECYCLING FLAG		
	W13	AREA IDENTIFICATION		
SIGN LOCATION LEGEND				

SIGN LOCATION LEGEND



WAYFINDING ELEVATIONS

HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE

SIGNAGE & WAYFINDING | ISSUED FOR BID



WAYFINDING AT ELEVATOR LOBBIES

C1 ELEVATOR EGRESS **C2** BUILDING DIRECTORY

<complex-block>

SITE VERIFY ALL ELEVATOR BANK CONDITIONS TO BE FREE OF OBSTRUCTIONS AND MOUNT ALIGNING AS SHOWN; FIELD MEASURE

> 2 ELEVATION @ FLOOR ENTRANCE SCALE: 3/8" = 1'0"

← 410 - 422

1 ELEVATION @ ELEVATOR BANK SCALE: 3/8" = 1' 0" W9B W9C OVERHEAD DIRECTIONAL ON GLASS TRANSOM



W4 WALL DIRECTIONAL



4 ELEVATION @ WALL DIRECTIONAL SCALE: 3/8" = 1' 0"

DEPARTMENT IDENTIFICATION






SITE VERIFY ALL OVERHEAD DOOR CONDITIONS AND FIELD MEASURE

ELEVATION @ DOUBLE DOOR DEPT/ROOM. ENTRANCE (1)SCALE: 3/8" = 1'0"

W8A DEPT ID





AND FIELD MEASURE

SCALE: 3/8" = 1'0"









SITE VERIFY ALL OVERHEAD DOOR CONDITIONS AND FIELD MEASURE

ELEVATION @ SINGLE DOOR DEPT. ENTRANCE

WAYFINDING IN STAIRWELL




C3 FLOOR DIRECTORY

1 STAIR B - FLOOR 4 SCALE: 3/8" = 1' 0" 2 STAIR A - FLOOR 4 SCALE: 3/8" = 1' 0"








SITE SURVEY AND CONFIRM LOCATIONS FOR ALL - TO BE FREE OF ANY OBSTRUCTIONS MOUNTING LOCATIONS TO BE AS CONSISTENT AS POSSIBLE FOR EACH FLOOR TOP PANEL ALIGNS WITH TOP OF PAINTED WALL.

DETAILS

HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE

SIGNAGE & WAYFINDING | ISSUED FOR BID





E 2, ELEVATOR BANK XX Ν XX THIS CAMPUS IS PROTECTED BY ELECTRONIC SURVEILLANCE

ALT LAYOUT W/ ELECTRONIC SURVEILLANCE MESSAGE

COLLEGE TO CONFIRM WHICH ELEVATOR BANKS WOULD REQUIRE THIS MESSAGE.

SIZE: 22" X 50-7/16"

APPLIED TO WALL

MATERIALS:

- 1/8" THICK HORIZONTAL SHORT GRAIN SATIN ALUMINUM EASED ALL EDGES
- HEIGHT AND DEPTH TO MATCH C1 BUILDING DIRECTORY
- ENGRAVED AND PAINT-FILLED TEXT AND TWO COLOR MAP
- LARGE NUMERAL: PANTONE 280 C •
- TEXT, RULE AND LOGO: TO MATCH MAP # 13795 "GRAYNOLA" •
- EGRESS MAP TO MATCH: MAP # 13795 "GRAYNOLA" AND RED (PANTONE 186)
- MATTE CLEAR COAT OVERALL

MOUNTING:

• Z-CLIPS @ TOP, CENTER AND BOTTOM OF PANEL, 2" IN FROM SIDE EDGES OF PANELS; ANCHORED TO BACK OF PANEL AND WALL. MOUNTING HARDWARE TO BE PROVIDED FOR REVIEW AND APPROVAL.

NOTE: FABRICATOR TO PROVIDE EGRESS MAP FOR EACH LEVEL BASED ON CURRENT MAP LAYOUT. FABRICATOR TO PROVIDE DRAWINGS FOR ALL FLOORS.

ELEVATOR EGRESS PANEL TO MATCH HEIGHT OF C2- BUILDING DIRECTORY


FIELD SURVEY TO CONFIRM ELEVATOR BANK IS FREE OF ANY OBSTRUCTIONS. FIELD MEASUREMENTS REQUIRED

2

C1 ELEVATOR EGRESS








SIDE VIEW - SIGN TYPE C1 SCALE: 1-1/2" = 1'-0"


DETAILS - C1 FLOOR ID/EGRESS MAP







DETAILS - C1A ELEVATOR EGRESS MAP



MATTE CLEAR COAT OVERALL

MOUNTING:


• FLUSH TO WALL WITH VHB TAPE AND SILICONE

NOTE: FABRICATOR TO PROVIDE EGRESS MAP FOR FINAL APPROVAL BASED ON DESIGN DIRECTION - THE CURRENT MAP IS FOR REFERENCE ONLY.



T-SQUARED DESIGN | 10.18.2022 | 35

DETAILS - C2 BUILDING DIRECTORY



SIZE: 22" X 50-7/16"

MATERIALS:

- APCO "ELEVATE" W/ 1/16" REVEAL BETWEEN SLATS
- 1/8" THICK HORIZONTAL SHORT GRAIN SATIN ALUMINUM
- 1ST SURFACE SCREEN PRINT COPY
- FLOOR NUMBERS: PANTONE 280C
- TEXT TO MATCH: MAP # 13795 "GRAYNOLA"
- FLOOR BAND: PANTONE 280 C NUMBER AND TEXT: WHITE

MOUNTING:

• Z-CLIPS @ TOP, CENTER AND BOTTOM OF PANEL, 2" IN FROM SIDE EDGES OF PANELS; ANCHORED TO BACK OF PANEL AND WALL

NOTE: THE COLLEGE TO CONFIRM ALL FINAL MESSAGES FOR THE DIRECTORY.

C2 BUILDING DIRECTORY








DETAILS - C2 BUILDING DIRECTORY




1 LAYOUTS SCALE: 3/4" = 1'-0"





DETAILS - C3 FLOOR DIRECTORY










DETAILS - C3 FLOOR DIRECTORY





ALIGN COLOR BAND WITH NUMERAL WITH PAINT LINE ON WALL




FIELD SURVEY TO CONFIRM AREA IS FREE OF ANY OBSTRUCTIONS. FIELD MEASUREMENTS REQUIRED / CONSISTENT LOCATION ON EACH FLOOR.





DETAILS - L1, L2A, L2B REGULATORY SIGNS








• 1/8" THICK HORIZONTAL SHORT GRAIN SATIN ALUMINUM

PAINT-FILLED TEXT AND LOGO TO MATCH MAP # 13795 "GRAYNOLA"



DETAILS - L3A, L3B, L3C REGULATORY SIGNS



L3A SMALL REGULATORY

SIGN TYPE L3A – FRONT ELEVATIONS SCALE: 3" = 1'-0"



MATERIALS:

- 1/8" THICK HORIZONTAL SHORT GRAIN SATIN ALUMINUM SMOOTH, EASED ALL EDGES
- ENGRAVED
- PAINT-FILLED TEXT AND LOGO TO MATCH MAP # 13795 "GRAYNOLA"
- MATTE CLEAR COAT OVERALL

MOUNTING:

FLUSH TO WALL WITH VHB TAPE AND SILICONE





L3B MEDIUM REGULATORY




SIZE: 8" X 6"

MATERIALS:

- 1/8" THICK HORIZONTAL SHORT GRAIN SATIN ALUMINUM SMOOTH, EASED ALL EDGES
- ENGRAVED
- PAINT-FILLED TEXT AND LOGO TO MATCH MAP # 13795 "GRAYNOLA"
- MATTE CLEAR COAT OVERALL

MOUNTING:

FLUSH TO WALL WITH VHB TAPE AND SILICONE





SIGN TYPE L3C - FRONT ELEVATIONS 5 SCALE: 3" = 1'-0"









SIZE: 9-5/8" X 13"

MATERIALS:

- 1/8" THICK HORIZONTAL SHORT GRAIN SATIN ALUMINUM SMOOTH, EASED ALL EDGES
- ENGRAVED
- PAINT-FILLED TEXT AND LOGO TO MATCH MAP # 13795 "GRAYNOLA"
- MATTE CLEAR COAT OVERALL
- JCC LOGO DIRECT PRINT

MOUNTING:

• FLUSH TO WALL WITH VHB TAPE AND SILICONE



DETAILS - L4, L5, L6, L7 REGULATORY SIGNS





1 SIGN TYPE L4 – FRONT ELEVATION SCALE: 3" = 1'-0"

SIZE: 6" X 6-1/2"

- 1/4" TH. ACRYLIC EASE AND SMOOTH EDGES PAINTED RED TO MATCH PMS 186
- SILKSCREEN TEXT WHITE

MOUNTING:

• FLUSH TO WALL WITH VHB TAPE AND SILICONE



L5 LARGE REGULATORY

2 SIGN TYPE L5 - FRONT ELEVATION

SCALE: 3" = 1'-0"

SIZE: 10-1/2" X 8"

- 1/4" TH. P95 ACRYLIC EASE AND SMOOTH EDGES
- PAINT TO BAND TO MATCH MAP # 13795 "GRAYNOLA" AND KNOCK OUT "DANGER" BACK-PAINTED PANEL "WHITE"
- SILKSCREEN TEXT TO MATCH MAP # 13795 "GRAYNOLA"

MOUNTING:

• FLUSH TO WALL WITH VHB TAPE AND SILICONE





^{3/4"} IN CASE OF FIRE USE NO WATER USE NO WATER NO STORAGE PERMITTED

L6 NO STORAGE


4 SIGN TYPE L6 - FRONT ELEVATION SCALE: 3" = 1'-0"

SIZE: 10-1/2" X 8"

- 1/4" TH. ACRYLIC EASE AND SMOOTH EDGES PAINTED RED TO MATCH PMS 186
- SILKSCREEN TEXT AND 1/8" TH. RULE WHITE

MOUNTING:

• FLUSH TO WALL WITH VHB TAPE AND SILICONE




L7 ELEVATOR MACHINE ROOM

5 SIGN TYPE L7 – FRONT ELEVATION SCALE: 3" = 1'-0"


SIZE: 2" CH.

- 3M DIE-CUT VINYL TO MATCH MAP # 13795 "GRAYNOLA"
- CENTER ON DOOR AND MOUNT @ 60" AFF TO TOP





DETAILS - R1, R2, R3, R4 ROOM IDENTIFICATION







SIZE: 8-1/2" X 8-1/2"


APCO FULLVIEW SERIES

MATERIALS:

- FVS8585(V)AB (SQUARE)
 - I.D. SIZE: 8 1/2" X 8 1/2"
 - COLOR: NATURAL SATIN
- SIGN INSERT:
 - HEADER PART CODE: NATURAL SATIN ANODIZED
 - SIZE: 2 3/8" X 8 1/2"
- DPT (DIRECT PRINT TACTILE) GRAPHICS:
 - COLOR: TO MATCH MAP # 13795 "GRAYNOLA"
- BRAILLE COLOR: SAME AS BACKGROUND
- PART CODE: SW PAPER & CLEARLENS
 - SIZE: 6 1/8" X 8 1/2"
 - PART COLOR: A01 WHITE
- LASERPRINTED GRAPHICS:
 - COLOR: TO MATCH MAP # 13795 "GRAYNOLA"
- COMPLETE SIGN AND GRAPHICS MANUFACTURED BY APCO

MOUNTING:

VHB AND SILICONE ADHESIVE



R2 CONFERENCE ROOM ID

SIGN TYPE R2 – FRONT ELEVATION 2 SCALE: 3" = 1'-0"

SIZE: 8-1/2" x 9-3/4"

- APCO FULLVIEW SERIES
- APCO SIGNBAND NOTIFIER MESSAGE STRIP W/ NATURAL SATIN ALUMINUM FINISH


MATERIALS:

- FVS8585(V)AB (SQUARE)
 - I.D. SIZE: 8 1/2" X 8 1/2"
 - COLOR: NATURAL SATIN
- SIGN INSERT:
 - HEADER PART CODE: NATURAL SATIN ANODIZED
 - SIZE: 2 3/8" X 8 1/2"
- DPT (DIRECT PRINT TACTILE) GRAPHICS:
- COLOR: TO MATCH MAP # 13795 "GRAYNOLA"
- BRAILLE COLOR: SAME AS BACKGROUND
- PART CODE: SW PAPER & CLEARLENS
 - SIZE: 6 1/8" X 8 1/2"
- PART COLOR: A01 WHITE
- LASERPRINTED GRAPHICS:
- COLOR: TO MATCH MAP # 13795 "GRAYNOLA"
- COMPLETE SIGN AND GRAPHICS MANUFACTURED BY APCO
- APCO SIGNBAND NOTIFIER MESSAGE STRIP W/ • NATURAL SATIN ALUMINUM FINISH

MOUNTING:

VHB AND SILICONE ADHESIVE







SIZE: 5" X 5-7/16"

MATERIALS:

MOUNTING:

SCALE: 3" = 1'-0"

4

SIGN TYPE R3 – FRONT ELEVATION SCALE: 3" = 1'-0"

SIZE: 5-1/8" X 6-3/16"

- APCO FULLVIEW SERIES
- APCO SIGNBAND NOTIFIER MESSAGE STRIP W/ NATURAL SATIN ALUMINUM FINISH


MATERIALS:


3

- FVS8585(V)AB (SQUARE)
 - I.D. SIZE: 5-1/8" X 5-1/8"
 - COLOR: NATURAL SATIN
- SIGN INSERT:
 - HEADER PART CODE: NATURAL SATIN ANODIZED
 - SIZE: 2 3/8" X 8 1/2"
- DPT (DIRECT PRINT TACTILE) GRAPHICS:
 - COLOR: TO MATCH MAP # 13795 "GRAYNOLA"
- BRAILLE COLOR: SAME AS BACKGROUND
- PART CODE: SW PAPER & CLEARLENS
 - SIZE: 2-1/2" X 5"
 - PART COLOR: A01 WHITE
- LASERPRINTED GRAPHICS:
 - COLOR: TO MATCH MAP # 13795 "GRAYNOLA"
- COMPLETE SIGN AND GRAPHICS MANUFACTURED BY APCO APCO SIGNBAND NOTIFIER MESSAGE STRIP W/ NATURAL SATIN ALUMINUM FINISH

MOUNTING:

VHB AND SILICONE ADHESIVE










SIGN TYPE R4 – FRONT ELEV AND SIDE VIEW




DETAILS - **R5, R5A, R6** ROOM IDENTIFICATION




• VHB TAPE AND SILICONE ADHESIVE

• VHB TAPE AND SILICONE ADHESIVE

MOUNTING:



DETAILS - R7, R8, R9 ROOM IDENTIFICATION



1 SIGN TYPE R7 – FRONT ELEVATION SCALE: 3" = 1'-0"

SIZE: 8-1/2" X 8-1/2" APCO FULLVIEW SERIES

MATERIALS:

- FVS8585(V)AB (SQUARE)
 - I.D. SIZE: 8 1/2" X 8 1/2"
 - COLOR: NATURAL SATIN
- SIGN INSERT:
 - HEADER PART CODE: NATURAL SATIN ANODIZED
 - SIZE: 2 3/8" X 8 1/2"
- DPT (DIRECT PRINT TACTILE) GRAPHICS:
 - COLOR: TO MATCH MAP # 13795 "GRAYNOLA"
 - BRAILLE COLOR: SAME AS BACKGROUND
- BOTTOM TACTILE PANEL
 - ICONS RAISED DPT GRAPHICS COLOR TO MATCH MAP # 13795 "GRAYNOLA"
 - ON WHITE BACKGROUND
- COMPLETE SIGN AND GRAPHICS MANUFACTURED BY APCO
- •
- SECONDARY (NON-TACTILE) PANEL: 8.5" w x 3" h
- 1/4" TH. P-95 ACRYLIC EASE AND SMOOTH EDGES
- BACK- PAINTED WHITE
- TEXT SILKSCREENED TO MATCH MAP #13795 "GRAYNOLA"

MOUNTING:

• VHB AND SILICONE ADHESIVE



2 SIGN TYPE R8 – FRONT ELEVATION SCALE: 3" = 1'-0"


MAIN ADA PANEL: 6" X 8-3/4"

- 1/4" THERMOFORMED PANEL, SUEDE FINISH, BACKPAINTED WHITE
- TACTILE THERMOFORMED LETTERS, TIPPED TO MATCH MAP#13795 "GRAYNOLA"
- TACTILE THERMOFORMED GRADE 2 BRAILLE, CLEAR

SECONDARY (NON-TACTILE) PANEL: 6" X 3"


- 1/4" TH. P-95 ACRYLIC EASE AND SMOOTH EDGES
- BACK- PAINTED WHITE
- TEXT SILKSCREENED TO MATCH MAP #13795 "GRAYNOLA"
- **MOUNTING:**

VHB TAPE AND SILICONE ADHESIVEE












4



R8 AND **R9** -TYPICAL INSTALLATION

SCALE: 3/8" = 1'-0"

5

DETAILS - **S8** EMERGENCY EXIT SIGN BAND



SIGN TYPE S8 – FRONT ELEVATION 1 SCALE: 3" = 1'-0"

MATERIALS:


- 1/8" TH. ACRYLIC EASE AND SMOOTH EDGES
- PAINTED RED TO MATCH PMS 186
- SILKSCREEN TEXT WHITE MATTE CLEAR COAT OVERALL

MOUNTING:

• FLUSH TO DOOR WITH VHB TAPE AND SILICONE

FIELD MEASURE:


• REVIEW AND MEASURE EACH LOCATION TO CONFIRM BAND WIDTH CAN WORK.











SIGN TYPE W4 – TYPICAL FRONT ELEVATION SCALE: 1-1/2" = 1'-0"

SIZE: 22" X 28"

• MATERIALS:


APCO "FULL VIEW" CHANGEABLE SIGN


- WITH NATURAL ALUMINUM FRAME COMPONENTS
 AND BACKGROUND PANEL
- DIGITALLY PRINTED PAPER INSERT -
- TEXT TO MATCH MAP # 13795 "GRAYNOLA"
- TOP BAND PANTONE 280C

MOUNTING:

• VHB AND SILICONE ADHESIVE

NOTE: FINAL LAYOUTS TO BE CONFIRMED BY COLLEGE





2 SIGN TYPE W5 – TYPICAL FRONT ELEVATION SCALE: 3" = 1'-0"

SIZE: 10" X 10"

MATERIALS:

- APCO "FULL VIEW" CHANGEABLE SIGN
- WITH NATURAL ALUMINUM FRAME COMPONENTS
 AND BACKGROUND PANEL
- DIGITALLY PRINTED PAPER INSERT -
- TEXT TO MATCH MAP # 13795 "GRAYNOLA"

MOUNTING:

•

• VHB AND SILICONE ADHESIVE

NOTE: FINAL LAYOUTS TO BE CONFIRMED BY COLLEGE




3



TYPICAL INSTALLATION ELEVATION

SCALE: 3/8" = 1'-0"

DETAILS - W8A DEPARTMENT IDENTIFICATION



W8A WALL MOUNTED DEPT/ROOM ID (@ DOUBLE DOORS)

SIGN TYPE W8A - TYPICAL FRONT ELEVATION SCALE: 1-1/2" = 1'-0"

SIZE: OVERALL VARIES PER SIGN TYPE

- TYPICAL 12" H. x WIDTH OF DOORS (INCLUDING FRAME)
- FIELD VERIFY ALL LOCATIONS PRIOR TO FABRICATION

MATERIALS:


- NUMBER/ARROW & END PANELS 1/4 TH. HORIZONTAL SHORT GRAIN SATIN ALUMINUM
- DEPARTMENT PANEL: 1/4" TH. P-95 ACRYLIC PANEL BACKPAINTED "WHITE" WITH 1/4" TH. P-95 ACRYLIC FACE AND RETURNS PAINTED
- DEPARTMENT NAME TO MATCH MAP #13795 "GRAYNOLA

MOUNTING:

SECURE P-95 ACRYLIC WITH 3M DUAL LOCK TO ALLOW CHANGEABILITY

NOTE: MATERIAL HARDWARE AND 3M DUAL LOCK TO BE PROVIDED FOR APPROVAL PRIOR TO FABRICATION.

SIGN TO ALIGN WITH DOOR FRAME. FIELD MEASUREMENTS REQUIRED AND SITE SURVEY PRIOR TO FABRICATION.








SIGNS TO ALIGN WITH DOOR FRAMES AS SHOWN - VIF

DETAILS - W8B, W8D AND W8E DEPARTMENT IDENTIFICATION



W8E WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR)

NOTE: MATERIAL HARDWARE AND 3M DUAL LOCK TO BE PROVIDED FOR APPROVAL PRIOR TO FABRICATION

 DEPARTMENT PANEL: 1/4" TH. P-95 ACRYLIC PANEL BACKPAINTED "WHITE" WITH 1/4" TH. P-95 ACRYLIC FACE AND RETURNS PAINTED DEPARTMENT NAME TO MATCH MAP #13795

SECURE P-95 ACRYLIC WITH 3M DUAL LOCK TO ALLOW CHANGEABILITY.

SIGN TO ALIGN WITH DOOR FRAME. FIELD MEASUREMENTS REQUIRED AND SITE SURVEY PRIOR TO FABRICATION.



"GRAYNOLA"

MOUNTING:



CHANGEABLE DEPT. NAME PANEL 1/4" TH. P-95 ACRYLIC - BACKPAINT WHITE



10'









SCALE: 3/8" = 1'-0"

DETAILS - W8C DEPARTMENT IDENTIFICATION

PLAN VIEW	1 1/4"	GLASS TRANSOM		
5 1/2"	· · · · · · · · · · · · · · · · · · ·			3M DUSTED CRYSTAL VINYL APPLIED FIRST SURFACE 12"
/	- 12"	59-1/2″ VIF TRIM ON SITE		
W8C DEF	T/ROOM ID (@ GLASS TRANSOM)			

SIGN TYPE W8C – TYPICAL FRONT ELEVATION

SCALE: 1-1/2" = 1'-0"

SIZE: OVERALL VARIES PER SIGN TYPE

- TYPICAL 12" H. x WIDTH OF GLASS TRANSOM
- FIELD VERIFY ALL LOCATIONS PRIOR TO FABRICATION

MATERIAL:


- NUMBER/ARROW PANEL 1/8 TH. HORIZONTAL SHORT GRAIN SATIN ALUMINUM
- DEPARTMENT NAME PANEL: DIRECT PRINT DEPARTMENT NAME TO MATCH MAP # 13795 ON 3M "DUSTED CRYSTAL" VINYL
- 1/4" TH ACRYLIC LETTERS PAINTED TO MATCH MAP # 13795 "GRAYNOLA"

MOUNTING:

- 3M "DUSTED CRYSTAL" VINYL APPIED FIRST SURFACE
- NUMBER/ARROW PANEL APPLIED TO GLASS W/ VHB TAPE, PROVIDE VINYL BACKER

NOTE: MATERIAL HARDWARE AND 3M DUAL LOCK TO BE PROVIDED FOR APPROVAL PRIOR TO FABRICATION.


SIGN TO ALIGN WITH DOOR FRAME. FIELD MEASUREMENTS REQUIRED AND SITE SURVEY PRIOR TO FABRICATION.







DETAILS - W9A OVERHEAD DIRECTIONAL



SIZE: OVERALL VARIES PER SIGN TYPE

- TYPICAL 12" H. x WIDTH OF DOORS (INCLUDING FRAME)
- FIELD VERIFY ALL LOCATIONS PRIOR TO FABRICATION

MATERIAL:

- ARROW END PANELS 1/4 TH. HORIZONTAL SHORT GRAIN SATIN ALUMINUM
- DEPARTMENT PANEL: 1/4" TH. P-95 ACRYLIC PANEL BACKPAINTED "WHITE" WITH 1/4" TH. P-95 ACRYLIC FACE AND RETURNS PAINTED
- DEPARTMENT NAME TO MATCH MAP #13795 "GRAYNOLA"

MOUNTING:

• SECURE P-95 ACRYLIC WITH 3M DUAL LOCK TO ALLOW CHANGEABILITY.

NOTE: MATERIAL HARDWARE AND 3M DUAL LOCK TO BE PROVIDED FOR APPROVAL PRIOR TO FABRICATION.


SIGN TO ALIGN WITH DOOR FRAME. FIELD MEASUREMENTS REQUIRED AND SITE SURVEY PRIOR TO FABRICATION.








DETAILS - W9B AND W9C OVERHEAD DIRECTIONALS








DETAILS - W10, W11, W12 FLAG SIGNS



SIZE: 14" X 10" X 3/4" TH. (TWO SIDED)


• MATERIALS:

P95 ACRYLIC - BACKPAINTED WHITE SILKSCREEN SYMBOL TO MATCH MAP # 13795 "GRAYNOLA"



6^{1/2"}

W10, W11, W12 – TYPICAL DETAILS 5 SCALE: 1-1/2" = 1'-0"



W11 DIRECTIONAL FLAG

SIGN TYPE W11 (DIRECTIONAL) 3 SCALE: 1-1/2" = 1'-0"

SIZE: 12" X 8-1/2" X 3/4" TH. (TWO SIDED)


MATERIALS:

4 ¹/16"

- P95 ACRYLIC BACKPAINTED WHITE SILKSCREEN TO MATCH MAP # 13795 "GRAYNOLA"
- @ TWO SIDES

MOUNTING:

CONCEALED FASTENERS



W10 RECYCLING FLAG

SIGN TYPE W12 (RECYCLING) 4 SCALE: 3" = 1'-0"


SIZE: 8-1/2" X 8-1/2" X 3/4" TH. (TWO SIDED)

MATERIALS:

- P95 ACRYLIC BACKPAINTED WHITE SILKSCREEN SYMBOL AND TEXT - GREEN
- DOUBLESIDED

MOUNTING:

CONCEALED FASTENERS







TYPICAL FLAG INSTALLATION ELEVATION


DETAILS - W13 LOCKER/FITNESS IDENTIFICATION

LOCKERS

W13 AREA IDENTIFICATION

FIELD MEASUREMENTS REQUIRED AND SITE SURVEY PRIOR TO FABRICATION.

1 W13 - AREA IDENTIFICATION SCALE: 1- 1/2" = 1'-0"



2 W13 - ELEV. @ ENTRANCE TO LOCKER ROOMS SCALE: 3/8" = 1'-0"








SIZE: 15-7/8" CH (VIF)

MATERIALS:

- 1/4" TH. LASER CUT ACRYLIC LETTERS
- FACE AND RETURNS PAINTED TO MATCH PMS 280

MOUNTING:

- BLIND STUD MOUNT TO WALL
- VERIFY SITE CONDITIONS



SIGN LAYOUTS

HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE

SIGNAGE & WAYFINDING | ISSUED FOR BID



C1 - FLOOR ID AND EGRESS MAP LAYOUTS







FLOOR 3 - LOCATION 121

FINAL EGRESS MAPS TO BE PROVIDED BY FABRICATOR EXISTING IS FOR REFERENCE ONLY. CORRECT ORIENTATION REQUIRED

C1 - FLOOR ID AND EGRESS MAP LAYOUTS



FINAL EGRESS MAPS TO BE PROVIDED BY FABRICATOR EXISTING IS FOR REFERENCE ONLY. CORRECT ORIENTATION REQUIRED



C2 – BUILDING DIRECTORY LAYOUTS







Marketing & Communications Office of Chief Diversity Officer/ Title IX Coordinator Office of the President Office of the Provost Tennis Court

Walkway to the New Building

FIELD SURVEY TO CONFIRM ELEVATOR BANK IS FREE OF ANY OBSTRUCTIONS. FIELD MEASUREMENTS REQUIRED

C2 - BUILDING DIRECTORY LAYOUTS




SIGN TYPE C2 - FLOORS 4, 5, 6 LAYOUTS SCALE: 1-1/2" = 1'-0"

> SUALE: 1-1/2" = 1



FIELD SURVEY TO CONFIRM ELEVATOR BANK IS FREE OF ANY OBSTRUCTIONS. FIELD MEASUREMENTS REQUIRED

C3 - FLOOR DIRECTORY LAYOUTS







Spectropy

221 Completion for Upperdates Sinch at Program

22e State i Mjusci Reem


25 A/22 B Williamy and New continuous


State of Adjunct Form

200 Facily Seals Office



research - search and they have







Contents Programs

Lookenic Program.

etti Carlenaso Rossi

ető Réfeilisseptent

FRANK & - LARN TRANK SIZE, TAN-





881 Fredin Services Mark degard Companiestices Office of hetitational Admession at

Namia Souri

STATES AND

No ette Roost

et 2 Office of Institutional Administree at

340 Land Council Calor Branchy Efford The D. Counciles


Ex Related Affilias

Storte Restort

604956 Orienti Jestin and Orienti Jestin PhD Rogram

manne-say was be, ind

L3A, L3B - SMALL AND MEDIUM REGULATORY SIGN LAYOUTS



SIGN TYPE **L3A** SMALL REGULATORY – LAYOUTS SCALE: 3" = 1'-0"


SIGN TYPE **L3B** MEDIUM REGULATORY – LAYOUTS 2 SCALE: 3" = 1'-0"



CAUTION WHEN LIGHTS FLASH, DO NOT USE STAIRCASE. STAIR CLIMBER IN USE



R7, R9 – LOCKER ROOM SIGN LAYOUTS




R7 LOCKER ROOM ID @ VARSITY LOCKER ROOMS SCALE: 3" = 1'-0"



R9 LOCKER ID 2 SCALE: 3" = 1'-0"



W4 - FLOORS 2 AND 3 FLOOR DIRECTIONALS




→ 210, 212, 230 - 238 Walkway to the New Building Shared Adjunct Room Faculty Senate Office Restrooms [™]

FLOOR 2 - LOCATION 117 SCALE: 1-1/2" = 1'-0"



FLOOR 3 - LOCATION 138 SCALE: 1-1/2" = 1'-0"



FLOOR 3 - LOCATION 139 SCALE: 1-1/2" = 1'-0"

← 212, 220 - 229

→ 210, 230 - 238

FLOOR 2 - LOCATION 139

SCALE: 1-1/2" = 1'-0"

Military and Veteran Service

Completion for Upperclass

Shared Adjunct Room

Student Program

Women's Restroom 🚺

Shared Adjunct Room

Faculty Senate Office

Men's Restroom 🚺

← 212, 220 - 229
 Military and Veteran Service
 Shared Adjunct Room
 Completion for Upperclass
 Student Program
 Women's Restroom
 ▲ 210, 230 - 238
 Shared Adjunct Room

Faculty Senate Office

Men's Restroom

FLOOR 2 - LOCATION 140 SCALE: 1-1/2" = 1'-0"

← 320 - 327
 Art and Music
 Women's Restroom

→ 330 - 336

Communications and Theater Arts Theater and Event Support Services Teaching and Learning Center Institutional Effectiveness Men's Restroom

FLOOR 3 - LOCATION 142 SCALE: 1-1/2" = 1'-0"





FLOOR 2- LOCATION 128 SCALE: 1-1/2" = 1'-0"



FLOOR 3 - LOCATION 132 SCALE: 1-1/2" = 1'-0"

W4 - FLOORS 4 AND 5 FLOOR DIRECTIONALS

Law, Police Science and

Criminal Justice Administration Athletics Annex Women's Restroom

← 420 - 423

\rightarrow 410, 413, 430 - 439 Athletics Gymnasium Student Academic Engagement & Retention Security, Fire and Emergency Management SEEK Department and Tutoring Labs Restrooms 👪

FLOOR 6 - LOCATION 102 SCALE: 1-1/2" = 1'-0"

← 413, 420 - 423

Law, Police Science and Criminal Justice Administration Athletics Annex Women's Restroom 🜆

→ 430 - 439 Office of Student Academic Engagement & Retention Security, Fire and Emergency Management SEEK Department and Tutoring Labs Men's Restroom 🚺

FLOOR 6 - LOCATION 132 SCALE: 1-1/2" = 1'-0"

← 520 - 523 Sociology Dispute Resolution Center Public Management

→ 530 - 533 Academic Programs Public Management Restrooms 👪

FLOOR 5 - LOCATION 133 SCALE: 1-1/2" = 1'-0"

← 520 - 523 Sociology **Dispute Resolution Center** Public Management Women's Restroom 🜆 → 530 - 533 Academic Programs Public Management Men's Restroom

FLOOR 5 - LOCATION 143 SCALE: 1-1/2" = 1'-0"

← 413, 420 - 423 Law, Police Science and Criminal Justice Administration Athletics Annex Women's Restroom 🚺

→ 430 - 439

Office of Student Academic Engagement & Retention Security, Fire and Emergency Management SEEK Department and Tutoring Labs Men's Restroom 🚺

FLOOR 6 - LOCATION 134 SCALE: 1-1/2" = 1'-0"

← 520 - 523 Sociology Dispute Resolution Center Public Management Women's Restroom 🔢

→ 530 - 533 Academic Programs Public Management Men's Restroom

FLOOR 5 - LOCATION 147 SCALE: 1-1/2" = 1'-0"





FLOOR 6 - LOCATION 119 SCALE: 1-1/2" = 1'-0"

	5
	520 - 530 Sociology Dispute Resolution Center Public Management Academic Programs Restrooms
→	532 - 533 Academic Programs Public Management

FLOOR 5- LOCATION 130 SCALE: 1-1/2" = 1'-0"

W4 - FLOOR 6 FLOOR DIRECTIONALS

6

 620 - 625
 Office of the President External Affairs
 Office of Institutional Effectiveness
 Office of Legal Counsel
 Office of Chief Diversity Officer/ Title IX Coordinator
 Office of the Provost
 601 - 636 Faculty Services

Acuity Services Marketing and Communications Office of Institutional Effectiveness Tennis Court Criminal Justice and Criminal Justice PhD Restrooms

FLOOR 6 - LOCATION 128 SCALE: 1-1/2" = 1'-0" ▲ 620 - 625
 Office of the President
 External Affairs
 Institutional Effectiveness
 Office of Legal Counsel
 Office of Chief Diversity Officer/ Title IX Coordinator
 Office of the Provost Women's Restroom
 ← 601
 Faculty Services
 Marketing and Communications
 Office of Institutional Effectiveness

FLOOR 6 - LOCATION 123 SCALE: 1-1/2" = 1'-0"

Tennis Court



↑ 630 - 636 Criminal Justice and Criminal Justice PhD Men's Restroom ¹⁶

ĥ

← 610 Conference Room

→ 601 Faculty Services Marketing and Communications Office of Institutional Effectiveness

FLOOR 6 - LOCATION 121 SCALE: 1-1/2" = 1'-0"

Tennis Court





FLOOR 6 - LOCATION 157 SCALE: 1-1/2" = 1'-0"


ALL LAYOUTS TO BE CONFIRMED AND APPROVED BY THE COLLEGE.

W5 - FLOORS C AND L DIRECTIONALS





FLOOR C - LOCATION 108 SCALE: 3" = 1'-0"

 \uparrow NEW BUILDING **C10** POOL




 \uparrow C35 PRINT SHOP





FLOOR C - LOCATION 114 SCALE: 3" = 1'-0"

FLOOR C - LOCATION 129 SCALE: 3" = 1'-0"



FLOOR C - LOCATION 134 SCALE: 3" = 1'-0"

 \uparrow **NEW BUILDING**

FLOOR L - LOCATION 106 SCALE: 3" = 1'-0"





W5 - FLOOR 1 DIRECTIONALS



SCALE: 3" = 1'-0"

FLOOR 1 - LOCATION 124 SCALE: 3" = 1'-0"


FLOOR 1 - LOCATION 127 SCALE: 3" = 1'-0"







W5 - FLOORS 3, 5 AND 6 DIRECTIONALS





FLOOR 6 - LOCATION 136 SCALE: 3" = 1'-0"

630 - 636.19

C35 Print Shop


W8A WALL MOUNTED DEPT/ROOM ID (@ DOUBLE DOORS) - CONFIRM WIDTH FLOOR C - LOCATION 131



W8A WALL MOUNTED DEPT/ROOM ID (@ DOUBLE DOORS) - CONFIRM WIDTH AND SITE CONDITIONS FLOOR L - LOCATION 136



T-SQUARED DESIGN | 10.18.2022 | 71



HAAREN HALL BUILDING - JOHN JAY COLLEGE OF CRIMINAL JUSTICE - INTERIOR SIGNAGE & WAYFINDING | ISSUED FOR BID

FLOOR 2 - LOCATION 149

Student Research and Creativity


W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - CONFIRM WIDTH


Shared Adjunct Room

W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - CONFIRM WIDTH


Shared Adjunct Room

W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - CONFIRM WIDTH





W9C OVERHEAD DIRECTIONAL ON GLASS TRANSOM - 70-3/4" WIDE FLOOR 3 - LOCATION 141



W8C DEPT/ROOM ID (@ GLASS TRANSOM) - 72" WIDE - NEW DOOR W/RENOVATION, CONFIRM WIDTH FLOOR 3 - LOCATION 124



W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) 40" WIDE, CONFIRM WIDTH FLOOR 3 - LOCATION 148




332 Theater and Event Support Services Annex

W8C DEPT/ROOM ID (@ GLASS TRANSOM) - 70-3/4" WIDE FLOOR 3 - LOCATION 128




W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 40" CONFIRM WIDTH FLOOR 3 - LOCATION 129



336 Dept. of Communication and Theater Arts **Theater and Event Support Services**

W8A WALL MOUNTED DEPT/ROOM ID (@ DOUBLE DOORS) - 76" WIDE FLOOR 3 - LOCATION 135








W9C OVERHEAD DIRECTIONAL ON GLASS TRANSOM - 71" WIDE FLOOR 4 - LOCATION 110



W9B OVERHEAD DIRECTIONAL ON GLASS TRANSOM - 70-3/4" WIDE FLOOR 4 - LOCATION 112




W9C OVERHEAD DIRECTIONAL ON GLASS TRANSOM - 70-3/4" WIDE FLOOR 4 - LOCATION 111




410 Office of Student Academic **Engagement & Retention**


W8C DEPT/ROOM ID (@ GLASS TRANSOM) - 71-1/2" WIDE FLOOR 4 - LOCATION 133




W8C DEPT/ROOM ID (@ GLASS TRANSOM) - 70-3/4" WIDE FLOOR 4 - LOCATION 129















W8E WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 14" HT. (VIF) FLOOR 4 - LOCATION 153




W8E WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 14" HT. (VIF) FLOOR 4 - LOCATION 152









W9C OVERHEAD DIRECTIONAL ON GLASS TRANSOM - 70-3/4" WIDE FLOOR 5 - LOCATION 146





FLOOR 5 - LOCATION 125







W8A WALL MOUNTED DEPT/ROOM ID (@ DOUBLE DOORS) - 76" WIDE FLOOR 5 - LOCATION 132




Public Management Annex

W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 40" WIDE

Academic Programs

W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 14" HT. (VIF)




W9B OVERHEAD DIRECTIONAL ON GLASS TRANSOM - 70-3/4" WIDE FLOOR 6 - LOCATION 143

Faculty Services Marketing and Communications Office of Institutional Advancement

SCALE 1-1/2" = 1'-0"


17 1/2"



W8A WALL MOUNTED DEPT/ROOM ID (@ DOUBLE DOORS) - CONFIRM WIDTH FLOOR 6 - LOCATION 163



W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 39-3/4" CONFIRM WIDTH FLOOR 6 - LOCATION 146



W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 40" WIDE FLOOR 6 - LOCATION 147




W8B WALL MOUNTED DEPT/ROOM ID (@ SINGLE DOOR) - 40" WIDE FLOOR 6 - LOCATION 148





W8C DEPT/ROOM ID (@ GLASS TRANSOM) - 70-3/4" WIDE



633 Department of Criminal Justice and **Criminal Justice PhD Program**

W8A WALL MOUNTED DEPT/ROOM ID (@ DOUBLE DOORS) - 76" WIDE



ROOM NAMES AND NOMENCLATURE

HAAREN HALL BUILDING JOHN JAY COLLEGE OF CRIMINAL JUSTICE

SIGNAGE & WAYFINDING | ISSUED FOR BID




CELLAR - NOMENCLATURE






FLOOR L - NOMENCLATURE












FLOOR 2 - NOMENCLATURE


























JOHN JAY COLLEGE OF CRIMINAL JUSTICE DASNY PROJECT 3475609999 SIGNAGE HAAREN HALL BUILDING SIGNAGE REMOVALS AS PER EXISTING SIGNAGE AUDIT

11/17/2022


NOTE:

THE SIGNAGE INSTALLER IS RESPONSIBLE FOR REMOVING AND DISPOSING OF ALL THE EXISTING SIGNAGE SHOWN IN THIS DOCUMENT AND DISPOSING OF IT AS DIRECTED BY THE OWNER. ALL EXISTING AREAS THAT ARE DAMAGED BY SIGNAGE REMOVALS OR NEW SIGNAGE INSTALLATIONS SHALL BE PATCHED AS REQUIRED TO MATCH EXISTING ADJACENT AREA IN MATERIAL, FINISH, AND COLOR. COLORS TO BE CONFIRMED BY THE OWNER. THE SIGNAGE INSTALLER MUST PROMPTLY INSTALL NEW SIGNAGE AS SOON AS THE EXISTING SIGNAGE IS REMOVED AND PATCHING IS COMPLETE.





































EXISTING SIGNAGE – BASEMENT






EXISTING SIGNAGE – BASEMENT











































 \backslash



























































T-SQUARED | 06.13.2018 | 25



















































































T-SQUARED | 06.13.2018 | 45

















































P


































































































Attachment C: Site Logistics

CUNY John Jay Haaren Hall Signage Project 3475609999

A. Project Overview:

1. Describe Project,

Fabrication and installation of the Interior signage and Wayfinding program for Haaren Hall spanning all floors, approximately 1140 signages. The contractor will coordinate removal, patch and repair of existing signage.

2. The project is located at: 899, 10th Avenue, New York, NY 10019

B. Site Visit, Conditions and Logistics:

- 1. All vendors are responsible for scheduling a site visit to assess logistical delivery issues and site conditions. DASNY shall presume all vendors have visited the project site and verified existing field conditions. All visits must be coordinated with the Mr. Ammar Abdul Hussein (DASNY PM) on cell: (646) 235-7961 Email: aabdulhu@dasny.org.
- 2. Each vendor shall be responsible for assessing all site logistics, including appropriate truck size, loading dock conditions and gate availability, and shall be responsible for providing and fitting equipment in locations, as required. All vendors shall assume full responsibility for all equipment and accessories required to unload furniture and/or equipment at the dock.
- 3. If the site is still under construction at the time of delivery and/or installation, all workers entering the site must wear the required Personal Protective Equipment (PPE) including safety vests, hard hats, work boots, etc., in accordance with OSHA and other authorities having jurisdiction.
- 4. All loading dock and/or elevator usage must be coordinated with DASNY/CM.

Dock and Site Restrictions:

- i. The loading dock accesses thru the Cellar only.
- ii. The loading dock can accommodate material for the days work.
- iii. There is multiple Double doors in each floors that can be used to move material into & from the construction area.
- iv. There is no interior access except to the construction area.
- 2. Vendors shall provide flagmen with vests during deliveries to direct pedestrian and vehicular traffic, as required.

CUNY John Jay Haaren Hall Signage Project 3475609999

- 3. Dumpsters are not available on-site. Vendors shall be responsible for daily removal of debris off site. All vendors shall be responsible for obeying all site rules and established protocol.
- 4. Installation work shall include unloading, unpacking, and delivering to respective floor locations.

C. <u>Elevator Information:</u>

<u>Service Elevator</u>
a. Cab Interior: 58" Wide x 96" Deep x 96" High
b. Doorway: 48" Wide x 84" High
c. Capacity: 4,000 LBS

At delivery, the vendor will be provided with scheduled use of the freight elevator located on the 58th street entrance. There are 4 passenger elevators in Harren Hall which is restricted for construction personnel.

- 1. Vendors are responsible for confirming the dimension of the elevator's cabs and doors before delivery.
- 2. Elevator protection: By vendors.

D. **Building Protection**:

- 1. The vendor shall be responsible for the protection of all access and work areas, including, but not limited to walls, doors etc., but not flooring. Flooring protection will be by the vendors. The vendor will be held responsible for the repair or replacement of any damage to the building, grounds, walls, and flooring due to the delivery and installation of the product.
- 2. All delivery paths (walls, etc.) will be protected and maintained, with paper and masonite. The utilization of steel-wheel dollies is prohibited.
- 3. Furniture/Equipment Protection: All furniture/equipment work surfaces shall be protected after installation is completed. The work surface protection shall be removed by others at a later date.

CUNY John Jay Haaren Hall Signage Project 3475609999

F. <u>Delivery Schedule:</u>

- 1. All deliveries shall occur from 6:00 am to 4:00 pm unless otherwise scheduled with DASNY.
- 2. The Vendor shall be responsible for coordinating permitting for their deliveries in the street as required
- 3. The Vendor shall be responsible for coordinating exact delivery dates and times with the project site. Only products that can be immediately installed in a completed space shall be delivered, to avoid staging and on-site storage. The Vendor shall be responsible for temporarily storing materials in a secure warehouse for a period of up to 30 days from DASNY's requested delivery date at no additional cost. The Vendor shall be responsible for the rejection of product delivery, replacement, repair or any other corrective action required, for items received damaged, soiled or not conforming to the detailed specifications.

G. <u>Tentative Fixtures, Furniture and Equipment Delivery Schedule:</u>

- 1. Installation of furniture is anticipated to begin in November of 2022.
- 2. Installation of fixtures and equipment can begin as indicated in the Request for Quotation and/or Invitation for Bid.

Note: Work must be completed by _____12-30-2023______.

H. <u>Supervision:</u>

1. A full-time Coordinating Project Manager and a minimum of one (1) Coordinating Superintendent/Foreman per floor shall be engaged while delivery and installation work are performed.

I. <u>Parking</u>:

1. On-site parking is not available.

J. <u>Punch list</u>:

- 1. Each vendor is responsible for contacting DASNY's designated representative at the end of each workday to review project status and obtain sign-off for daily work.
- 2. The furniture/equipment vendor shall schedule a punch list review with DASNY's designated representative. DASNY reserves the right to withhold 5% payment pending resolution of open punch list items.

CUNY John Jay Haaren Hall Signage Project 3475609999

SECURITY REQUIREMENTS

- A. Who will control access to the facility only; any/all site security is the responsibility of each vendor. CUNY will control access to the facility. Vendors are responsible to obtain security clearance from Campus Security.
- B. All Contractors shall submit Daily Reports to Ammar Abdul Hussein (**aabdulhu@dasny.org**) by 10:00 am the following day. Daily Reports are to record, at the minimum, the date, temperature, weather conditions, number of workforces, subcontractors, work activities and location, and special observations. Submission of Daily Reports to Julia Garzon will be a condition of monthly payments to the Contractor.
- C. Every Construction personal needs to get cleared at the front desk by Public Safety Presenting State ID & COVID vaccination card.

SPECIAL PROVISIONS

- A. This is a designated Hard Hat Project.
- B. There shall be no eating in the work area.
- C. Smoking is not permitted in the building, near air intakes, or within 30 feet of any building entrance or outdoor-air intakes.
- D. Use of alcohol and controlled substances on the project site is not permitted.
- E. Contractors are to comply with OMH's Rules/Regulations for Vendors and Contractors.
- F. No signs or advertising material will be permitted on the job site.
- G. All provisions of all applicable State Labor Standards must be complied with under provisions of this contract. In addition to the PLA agreement.