ADDENDUM NO.: 3
IFB or RFP NO.: 740
Description: Furnish, Deliver and Install Cisco Product
Project: CUNY Central Office
Bid Opening Date: February 24, 2023

Specifics of the Addendum: Extend the Bid Opening Date, provide responses to the additional Requests for Information, and to provide a revised Detailed Specifications and Bid Breakdown & Schedule.

Extension to Bid Opening: Please see the following change to the Notice and Information for Bidders:

Section 1.0 – Notice to Bidders & Bid Opening and Attachment A: Bid Breakdown & Schedule

The bid opening scheduled for February 17, 2023 at 2:00 p.m. has been **rescheduled to February 24, 2023 at 2:30 p.m.**

Please see responses to the additional requests for information below:

1Q: Original RFP had the same number of AP's as current & planned (235). Now the current shows 222. I want to confirm that for this phase of the RFP we are only doing a one for one replacement. No new AP mounting is required. Is that correct?

1A: *Correct – Initially (1) for (1) replacement. If the post-install WIFI surveys show the need for additional WAPs then we are asking the winning vendor to assist with mounting them. All cabling will be supplied by CUNY.*

2Q: Page 5 of Addendum 2 shows attachment A & B. Line 66 is different between them. Please confirm attachment A should match attachment B and that part should be inserted before line containing "N9K-C93180-FX3-B8C".

2A: *Yes, Attachment A should match Attachment B.   See revised Bid Breakdown & Schedule and Detailed Specifications below and attached.*

3Q   Do you want redundant power supplies for your 9800 wireless controllers? Line 43 shows a blank face plate for where a redundant power supply would go and only 4 power cords were ordered (line 45).

However, line 47 shows redundant power supplies. If you want redundant power supplies, line 43 "C9800-PWR-BLANK" should be deleted and line 45 should be doubled to 8.

3A.   See revised Bid Breakdown & Schedule and revised Detailed Specifications below and attached.

4Q: Please confirm, all equipment moving from and back to 395 Hudson to the other 2 sites must be union labor taking equipment to/from the loading dock?

4A.   Everyone coming into 395 Hudson Street location must present a valid and active union labor membership card in order to come onto the property.

REVISED Attachment A: Bid Breakdown & Schedule – SEE ATTACHED

Item No.	Part No.	Description	QTY	UOM	Unit Price	Extended Price
43	ITEM REMOVED	ITEM REMOVED: Cisco 9800 Wireless Controller PS Blank			$	$
44	CAB-C13-C14-2M	Power Cord Jumper, C13-C14 Connectors, 2 Meter Length	8	EA	$	$
65	SFP-10G-SR-S=	10GBASE-SR SFP Module, Enterprise-Class	4	EA	$	$
66	N9K-C93180-FX3-B8C	2xNexus 93180YC-FX3 w/ 8x 100G Optics	4	EA	$	$

REVISED Attachment B: Detailed Specifications – SEE ATTACHED

Item No.	Part Number	Description	Term (mos)	Qty
43	ITEM REMOVED	ITEM REMOVED: Cisco 9800 Wireless Controller PS Blank	---	4
44	CAB-C13-C14-2M	Power Cord Jumper, C13-C14 Connectors, 2 Meter Length	---	8
65	SFP-10G-SR-S=	10GBASE-SR SFP Module, Enterprise-Class	---	4
Distribution				
66	**N9K-C93180-FX3-B8C**	2xNexus 93180YC-FX3 w/ 8x 100G Optics	---	4

All other terms and conditions of the original Invitation for Bids shall remain the same.

BIDDING REQUIREMENTS for PURCHASING

NOTICE AND INFORMATION FOR BIDDERS

Attachment A: Bid Breakdown & Schedule

Bidder: _____

DASNY Contact: Susan Valente, Purchasing Coordinator: svalente@dasny.org

Services/Product Required By: Delivery of Product and Install to be scheduled as soon as possible based on product lead time.

Description: Furnish, Deliver and Install Cisco Product

Bid Open Location: DASNY, Corporate Headquarters, 515 Broadway, Albany, NY 12207

Bid Open Date and Time: February 24, 2023 at 2:30 p.m.

Item No.	Part No.	Description	QTY	UOM	Unit Price	Extended Price
1	C9300X-48HX-E	Catalyst 9300 48-port mGig UPoE+, Network Essentials	106	EA	$	$
2	C9300-NW-E-48	C9300 Network Essentials, 48-port license	106	EA	$	$
3	SC9300UK9-176	Cisco Catalyst 9300 XE 17.6 UNIVERSAL UNIVERSAL	106	EA	$	$
4	PWR-C1-1100WAC-P	1100W AC 80+ platinum Config 1 Power Supply	106	EA	$	$
5	PWR-C1-1100WAC-P/2	1100W AC 80+ platinum Config 1 Secondary Power Supply	106	EA	$	$
6	CAB-C15-CBN	Cabinet Jumper Power Cord, 250 VAC 13A, C14-C15 Connectors	212	EA	$	$
7	C9300-SSD-NONE	No SSD Card Selected	106	EA	$	$
8	STACK-T1-50CM	50CM Type 1 Stacking Cable	106	EA	$	$
9	CAB-SPWR-30CM	Catalyst Stack Power Cable 30 CM	106	EA	$	$
10	C9000-HSEC	U.S. Export Restriction Compliance license for Catalyst 9000	106	EA	$	$
11	C9300-DNA-E-48	C9300 DNA Essentials, 48-Port Term Licenses	106	EA	$	$
12	C9300-DNA-E-48-3Y	C9300 DNA Essentials, 48-port - 3 Year Term License	106	EA	$	$
13	NETWORK-PNP-LIC	Network Plug-n-Play Connect for zero-touch device deployment	106	EA	$	$
14	C9300X-NM-BLANK	Catalyst 9300 Network Module Blank Module	106	EA	$	$
15	C9300X-NM-NONE	Catalyst 9300 No-Network Module Selection	106	EA	$	$
16	C9300X-NM-8Y=	Catalyst 9300 8 x 10G/25G Network Module SFP+/SFP28	78	EA	$	$
17	SFP-10/25G-CSR-S=	Dual Rate 10/25GBASE-CSR SFP Module	170	EA	$	$
18	STACK-T1-1M=	1M Type 1 Stacking Cable	12	EA	$	$
19	CAB-SPWR-150CM=	Catalyst Stack Power Cable 150 CM Spare	12	EA	$	$
20	ALC-DNAC-OFFER	Requires Advantage or Premier Subscription Purchase	1	EA	$	$
21	DN2-HW-APL-XL-U	DNA Center Appliance (Gen 2)- 112 core for Promos	1	EA	$	$
22	DNA-SW-2.2.3	Cisco DNA Center SW 2.2.3	1	EA	$	$
23	CAB-C13-C14-2M	Power Cord Jumper, C13-C14 Connectors, 2 Meter Length	2	EA	$	$

24	DN2-PCIE-ID10GF	Intel X710-DA2 dual-port 10G SFP+ NIC	1	EA	$	$
25	DN2-SD-64G-S	64GB SD Card for UCS Servers	1	EA	$	$
26	DN2-TPM2-002	Trusted Platform Module 2.0 for UCS servers	1	EA	$	$
27	DN2-SD38T61X-EV	3.8TB 2.5 inch Enterprise Value 6G SATA SSD	2	EA	$	$
28	DN2-C480-8HDD	UCS C480 M5 Drive Module for 8x HDD	3	EA	$	$
29	DN2-C480-CM	UCS C480 M5 CPU Module w/o CPU, mem	2	EA	$	$
30	DN2-MSTOR-SD	Mini Storage Carrier for SD (holds up to 2)	1	EA	$	$
31	DN2-PSU1-1600W	Cisco UCS 1600W AC Power Supply for Rack Server	4	EA	$	$
32	DN2-RAID-M5HD	Cisco 12G Modular RAID controller with 4GB cache	1	EA	$	$
33	DN2-PCIE-IQ10GF	Intel X710 quad-port 10G SFP+ NIC	1	EA	$	$
34	DN2-SD19T61X-EV	1.9TB 2.5 inch Enterprise Value 6G SATA SSD	16	EA	$	$
35	DN2-SD480G6I1X-EV	480GB 2.5 inch Enterprise Value 6G SATA SSD	2	EA	$	$
36	DN2-MR-X32G2RT-H	32GB DDR4-2933-MHz RDIMM/2Rx4/1.2v	24	EA	$	$
37	DN2-CPU-I8276	Intel 8276 2.2GHz/165W 28C/38.50MB DCP DDR4 2933 MHz	4	EA	$	$
38	DN2-HW-APL-XL-LIC	Cisco DNAC Appliance License- 112 Core	1	EA	$	$
39	SFP-10G-SR-S=	10GBASE-SR SFP Module, Enterprise-Class	12	EA	$	$
40	C9800-40-K9	Cisco Catalyst 9800-40 Wireless Controller	4	EA	$	$
41	LIC-C9800-DTLS-K9	Cisco Catalyst 9800 Series Wireless Controller DTLS License	4	EA	$	$
42	SC980040K9-173	Cisco Catalyst 9800-40 Wireless Controller	4	EA	$	$
43	C9800-AC-750W-R	Cisco Catalyst 9800-40 750W AC Power Supply	4	EA	$	$
44	CAB-C13-C14-2M	Power Cord Jumper, C13-C14 Connectors, 2 Meter Length	8	EA	$	$
45	NETWORK-PNP-LIC	Network Plug-n-Play Connect for zero-touch device deployment	4	EA	$	$
46	C9800-AC-750W-RED	Cisco Catalyst 9800-40 750W AC Power Supply	4	EA	$	$
47	CW9166I-B	Catalyst 9166I AP (W6E, tri-band 4x4, XOR) w/Reg-B	350	EA	$	$
48	SW9166-CAPWAP-K9	Capwap software for Catalyst 9166I	350	EA	$	$
49	AIR-AP-T-RAIL-R	Ceiling Grid Clip for APs & Cellular Gateways-Recessed	350	EA	$	$
50	AIR-AP-BRACKET-1	802.11 AP Low Profile Mounting Bracket (Default)	350	EA	$	$
51	CDNA-A-C9166	Wireless Cisco DNA On-Prem Advantage, 9166 Tracking	350	EA	$	$
52	DNA-A-3Y-C9166	C166I Cisco DNA On-Prem Advantage,3Y Term,Trk Lic	350	EA	$	$
53	AIR-DNA-A	Wireless Cisco DNA On-Prem Advantage, Term Lic	350	EA	$	$
54	AIR-DNA-A-3Y	Wireless Cisco DNA On-Prem Advantage, 3Y Term Lic	350	EA	$	$
55	PI-LFAS-AP-T	Prime AP Term Licenses	350	EA	$	$
56	PI-LFAS-AP-T-3Y	PI Dev Lic for Lifecycle & Assurance Term 3Y	350	EA	$	$
57	AIR-DNA-A-T	Wireless Cisco DNA On-Prem Advantage, Term, Tracker Lic	350	EA	$	$
58	AIR-DNA-A-T-3Y	Wireless Cisco DNA On-Prem Advantage,	350	EA	$	$

		3Y Term, Tracker Lic			$	$
59	AIR-DNA-NWSTACK-A	AIR CISCO DNA Perpetual Network Stack	350	EA	$	$
60	D-CISCODNAS-ACT-T	Cisco DNA Spaces Act Term License for Cisco DNA	350	EA	$	$
61	D-CISCODNAS-ACT-3Y	Cisco DNA Spaces ACT for Cisco DNA - 3Year	350	EA	$	$
62	NETWORK-PNP-LIC	Network Plug-n-Play Connect for zero-touch device deployment	350	EA	$	$
63	CW9166I-SINGLE	SINGLE PACK OPTION	350	EA	$	$
64	CW9166I-OVER	C9166I OVER OPTION	350	EA	$	$
65	SFP-10G-SR-S=	10GBASE-SR SFP Module, Enterprise-Class	4	EA	$	$
66	N9K-C93180-FX3-B8C	2xNexus 93180YC-FX3 w/ 8x 100G Optics	4	EA	$	$
67	NXK-AF-PE	Dummy PID for Airflow Selection Port-side Exhaust	8	EA	$	$
68	MODE-NXOS	Dummy PID for mode selection	8	EA	$	$
69	N9K-C93180YC-FX3B	Nexus 93180YC-FX3 bundle PID	4	EA	$	$
70	NXOS-9.3.9	Nexus 9500, 9300, 3000 Base NX-OS Software Rel 9.3.9	4	EA	$	$
71	NXK-MEM-16GB	Additional memory of 16GB for Nexus Switches	4	EA	$	$
72	NXK-ACC-KIT-1RU	Nexus 3K/9K Fixed Accessory Kit, 1RU front and rear removal	4	EA	$	$
73	NXA-FAN-35CFM-PE	Nexus Fan, 35CFM, port side exhaust airflow	16	EA	$	$
74	NXA-PAC-650W-PE	Nexus NEBs AC 650W PSU - Port Side Exhaust	8	EA	$	$
75	CAB-C13-C14-AC	Power cord, C13 to C14 (recessed receptacle), 10A	8	EA	$	$
76	NXK-PICK-BIDI	PID to select QSFP-40/100-SRBD Optic in the bundle	4	EA	$	$
77	QSFP-40/100-SRBD	100G and 40GBASE SR-BiDi QSFP Transceiver, LC, 100m OM4 MMF	16	EA	$	$
78	N9K-C93180YC-FX3B	Nexus 93180YC-FX3 bundle PID	4	EA	$	$
79	NXOS-9.3.9	Nexus 9500, 9300, 3000 Base NX-OS Software Rel 9.3.9	4	EA	$	$
80	NXK-MEM-16GB	Additional memory of 16GB for Nexus Switches	4	EA	$	$
81	NXK-ACC-KIT-1RU	Nexus 3K/9K Fixed Accessory Kit, 1RU front and rear removal	4	EA	$	$
82	NXA-FAN-35CFM-PE	Nexus Fan, 35CFM, port side exhaust airflow	16	EA	$	$
83	NXA-PAC-650W-PE	Nexus NEBs AC 650W PSU - Port Side Exhaust	8	EA	$	$
84	CAB-C13-C14-AC	Power cord, C13 to C14 (recessed receptacle), 10A	8	EA	$	$
85	NXK-PICK-BIDI	PID to select QSFP-40/100-SRBD Optic in the bundle	4	EA	$	$
86	QSFP-40/100-SRBD	100G and 40GBASE SR-BiDi QSFP Transceiver, LC, 100m OM4 MMF	16	EA	$	$
87	C1A1TN9300XF-3Y	DCN Advantage Term N9300 XF, 3Y	8	EA	$	$
88	SVS-B-N9K-ADV-XF	EMBEDDED SOLN SUPPORT SWSS FOR ACI NEXUS 9K	8	EA	$	$
89	CON-CXS-XA-SPEC	Cisco Advanced Specialty Engineering Services – 500 hours		LS	$	$
90		Union Labor* – Installation at 395 Hudson Street – Certified Cisco Installer		LS	$	$
91		Non-Union Labor* – Installation at 205 East 42nd Street - Certified Cisco Installer		LS	$	$

92		Non-union Labor* – Installation at 555 West 57th Street - Certified Cisco Installer		LS	$	$

*Bidder to provide cost breakdown of labor per location, including number of hours and rate per hour.

Total Materials/Equipment/Commodities: $_____

Total Installation: $_____

TOTAL BID: $_____

(The below questions 1) and 2) need only be answered if the above total bid is for one million dollars or more)
1. Does your firm anticipate the use of subcontractors and outside suppliers specific to this procurement
    Yes ☐   No ☐
2. Does your firm anticipate the creation of employment opportunities arising from this procurement?
    Yes ☐   No ☐
(The below information must be completed for all bids.)
Identify all subcontractors, if any: _____

STATE, PROVINCE FOR FOREIGN COUNTRY
THAT YOUR FIRM'S PRINCIPAL PLACE OF
BUSINESS IS LOCATED:

_____

ADDRESS OF FACTORY OR PLANT WHERE
ITEMS ARE MANUFACTURED AND/OR
ASSEMBLED. *(Attach additional sheet(s) if more
than one manufacturer)*

_____
_____
_____
_____

_____
BIDDER (FIRM NAME)

_____
SIGNATURE

_____
NAME (TYPE/PRINTED)

_____
TITLE

_____
Date

Attachment B: Detailed Specifications

Bidder must be a certified Cisco reseller/distributor to provide the product and installation services requested in this Bid.

Active union cards are required and will need to be presented to provide delivery and installation services at CUNY's 395 Hudson Street location.

All vendor personnel entering CUNY sites must be fully vaccinated for COVID-19 and be willing to fully comply with CUNY's COVID-19 policy: Visitor Policy – The City University of New York (cuny.edu) This includes be willing to provide proof of vaccination via CUNY's portal: https://www.c4wrk.com/3fkvMuVn7UKDC1D3A

The awarded vendor will be required to provide satisfactory Certificates of Insurance (COIs), Hold harmless and any other required agreements relative to the leased space at the locations referenced below in Attachment C - Scope of Work, Section 2 – Locations in Scope.

Item No.	Part Number	Description	Term (mos)	Qty
		Access		
1	**C9300X-48HX-E**	Catalyst 9300 48-port mGig UPoE+, Network Essentials	---	106
2	C9300-NW-E-48	C9300 Network Essentials, 48-port license	---	106
3	SC9300UK9-176	Cisco Catalyst 9300 XE 17.6 UNIVERSAL UNIVERSAL	---	106
4	PWR-C1-1100WAC-P	1100W AC 80+ platinum Config 1 Power Supply	---	106
5	PWR-C1-1100WAC-P/2	1100W AC 80+ platinum Config 1 Secondary Power Supply	---	106
6	CAB-C15-CBN	Cabinet Jumper Power Cord, 250 VAC 13A, C14-C15 Connectors	---	212
7	C9300-SSD-NONE	No SSD Card Selected	---	106
8	STACK-T1-50CM	50CM Type 1 Stacking Cable	---	106
9	CAB-SPWR-30CM	Catalyst Stack Power Cable 30 CM	---	106
10	C9000-HSEC	U.S. Export Restriction Compliance license for Catalyst 9000	---	106
11	C9300-DNA-E-48	C9300 DNA Essentials, 48-Port Term Licenses	---	106
12	C9300-DNA-E-48-3Y	C9300 DNA Essentials, 48-port - 3 Year Term License	36	106
13	NETWORK-PNP-LIC	Network Plug-n-Play Connect for zero-touch device deployment	---	106
14	C9300X-NM-BLANK	Catalyst 9300 Network Module Blank Module	---	106
15	C9300X-NM-NONE	Catalyst 9300 No-Network Module Selection	---	106
16	**C9300X-NM-8Y=**	Catalyst 9300 8 x 10G/25G Network Module SFP+/SFP28	---	78
17	**SFP-10/25G-CSR-S=**	Dual Rate 10/25GBASE-CSR SFP Module	---	170
18	**STACK-T1-1M=**	1M Type 1 Stacking Cable	---	12
19	**CAB-SPWR-150CM=**	Catalyst Stack Power Cable 150 CM Spare	---	12
20	**ALC-DNAC-OFFER**	Requires Advantage or Premier Subscription Purchase	---	1
21	DN2-HW-APL-XL-U	DNA Center Appliance (Gen 2)- 112 core for Promos	---	1
22	DNA-SW-2.2.3	Cisco DNA Center SW 2.2.3	---	1
23	CAB-C13-C14-2M	Power Cord Jumper, C13-C14 Connectors, 2 Meter Length	---	2
24	DN2-PCIE-ID10GF	Intel X710-DA2 dual-port 10G SFP+ NIC	---	1

25	DN2-SD-64G-S	64GB SD Card for UCS Servers	---	1
26	DN2-TPM2-002	Trusted Platform Module 2.0 for UCS servers	---	1
27	DN2-SD38T61X-EV	3.8TB 2.5 inch Enterprise Value 6G SATA SSD	---	2
28	DN2-C480-8HDD	UCS C480 M5 Drive Module for 8x HDD	---	3
29	DN2-C480-CM	UCS C480 M5 CPU Module w/o CPU, mem	---	2
30	DN2-MSTOR-SD	Mini Storage Carrier for SD (holds up to 2)	---	1
31	DN2-PSU1-1600W	Cisco UCS 1600W AC Power Supply for Rack Server	---	4
32	DN2-RAID-M5HD	Cisco 12G Modular RAID controller with 4GB cache	---	1
33	DN2-PCIE-IQ10GF	Intel X710 quad-port 10G SFP+ NIC	---	1
34	DN2-SD19T61X-EV	1.9TB 2.5 inch Enterprise Value 6G SATA SSD	---	16
35	DN2-SD480G6I1X-EV	480GB 2.5 inch Enterprise Value 6G SATA SSD	---	2
36	DN2-MR-X32G2RT-H	32GB DDR4-2933-MHz RDIMM/2Rx4/1.2v	---	24
37	DN2-CPU-I8276	Intel 8276 2.2GHz/165W 28C/38.50MB DCP DDR4 2933 MHz	---	4
38	DN2-HW-APL-XL-LIC	Cisco DNAC Appliance License- 112 Core	---	1
39	SFP-10G-SR-S=	10GBASE-SR SFP Module, Enterprise-Class	---	12
	WLAN			
40	**C9800-40-K9**	Cisco Catalyst 9800-40 Wireless Controller	---	4
41	LIC-C9800-DTLS-K9	Cisco Catalyst 9800 Series Wireless Controller DTLS License	---	4
42	SC980040K9-173	Cisco Catalyst 9800-40 Wireless Controller	---	4
43	C9800-AC-750W-R	Cisco Catalyst 9800-40 750W AC Power Supply	---	4
44	CAB-C13-C14-2M	Power Cord Jumper, C13-C14 Connectors, 2 Meter Length	---	8
45	NETWORK-PNP-LIC	Network Plug-n-Play Connect for zero-touch device deployment	---	4
46	C9800-AC-750W-RED	Cisco Catalyst 9800-40 750W AC Power Supply	---	4
47	**CW9166I-B**	Catalyst 9166I AP (W6E, tri-band 4x4, XOR) w/Reg-B	---	350
48	SW9166-CAPWAP-K9	Capwap software for Catalyst 9166I	---	350
49	AIR-AP-T-RAIL-R	Ceiling Grid Clip for APs & Cellular Gateways-Recessed	---	350
50	AIR-AP-BRACKET-1	802.11 AP Low Profile Mounting Bracket (Default)	---	350
51	CDNA-A-C9166	Wireless Cisco DNA On-Prem Advantage, 9166 Tracking	---	350
52	DNA-A-3Y-C9166	C166I Cisco DNA On-Prem Advantage,3Y Term,Trk Lic	36	350
53	AIR-DNA-A	Wireless Cisco DNA On-Prem Advantage, Term Lic	---	350
54	AIR-DNA-A-3Y	Wireless Cisco DNA On-Prem Advantage, 3Y Term Lic	36	350
55	PI-LFAS-AP-T	Prime AP Term Licenses	---	350
56	PI-LFAS-AP-T-3Y	PI Dev Lic for Lifecycle & Assurance Term 3Y	36	350
57	AIR-DNA-A-T	Wireless Cisco DNA On-Prem Advantage, Term, Tracker Lic	---	350
58	AIR-DNA-A-T-3Y	Wireless Cisco DNA On-Prem Advantage, 3Y Term, Tracker Lic	36	350
59	AIR-DNA-NWSTACK-A	AIR CISCO DNA Perpetual Network Stack	---	350
60	D-CISCODNAS-ACT-T	Cisco DNA Spaces Act Term License for Cisco DNA	---	350
61	D-CISCODNAS-ACT-3Y	Cisco DNA Spaces ACT for Cisco DNA - 3Year	36	350
62	NETWORK-PNP-LIC	Network Plug-n-Play Connect for zero-touch device deployment	---	350
63	CW9166I-SINGLE	SINGLE PACK OPTION	---	350
64	CW9166I-OVER	C9166I OVER OPTION	---	350

65	SFP-10G-SR-S=	10GBASE-SR SFP Module, Enterprise-Class	---	4
		Distribution		
66	**N9K-C93180-FX3-B8C**	2xNexus 93180YC-FX3 w/ 8x 100G Optics	---	4
67	NXK-AF-PE	Dummy PID for Airflow Selection Port-side Exhaust	---	8
68	MODE-NXOS	Dummy PID for mode selection	---	8
69	N9K-C93180YC-FX3B	Nexus 93180YC-FX3 bundle PID	---	4
70	NXOS-9.3.9	Nexus 9500, 9300, 3000 Base NX-OS Software Rel 9.3.9	---	4
71	NXK-MEM-16GB	Additional memory of 16GB for Nexus Switches	---	4
72	NXK-ACC-KIT-1RU	Nexus 3K/9K Fixed Accessory Kit, 1RU front and rear removal	---	4
73	NXA-FAN-35CFM-PE	Nexus Fan, 35CFM, port side exhaust airflow	---	16
74	NXA-PAC-650W-PE	Nexus NEBs AC 650W PSU - Port Side Exhaust	---	8
75	CAB-C13-C14-AC	Power cord, C13 to C14 (recessed receptacle), 10A	---	8
76	NXK-PICK-BIDI	PID to select QSFP-40/100-SRBD Optic in the bundle	---	4
77	QSFP-40/100-SRBD	100G and 40GBASE SR-BiDi QSFP Transceiver, LC, 100m OM4 MMF	---	16
78	N9K-C93180YC-FX3B	Nexus 93180YC-FX3 bundle PID	---	4
79	NXOS-9.3.9	Nexus 9500, 9300, 3000 Base NX-OS Software Rel 9.3.9	---	4
80	NXK-MEM-16GB	Additional memory of 16GB for Nexus Switches	---	4
81	NXK-ACC-KIT-1RU	Nexus 3K/9K Fixed Accessory Kit, 1RU front and rear removal	---	4
82	NXA-FAN-35CFM-PE	Nexus Fan, 35CFM, port side exhaust airflow	---	16
83	NXA-PAC-650W-PE	Nexus NEBs AC 650W PSU - Port Side Exhaust	---	8
84	CAB-C13-C14-AC	Power cord, C13 to C14 (recessed receptacle), 10A	---	8
85	NXK-PICK-BIDI	PID to select QSFP-40/100-SRBD Optic in the bundle	---	4
86	QSFP-40/100-SRBD	100G and 40GBASE SR-BiDi QSFP Transceiver, LC, 100m OM4 MMF	---	16
87	C1A1TN9300XF-3Y	DCN Advantage Term N9300 XF, 3Y	36	8
88	SVS-B-N9K-ADV-XF	EMBEDDED SOLN SUPPORT SWSS FOR ACI NEXUS 9K	36	8
		Implementation/Installation Services		
89	CON-CXS-XA-SPEC	Cisco Advanced Specialty Engineering Services – 500 hours	---	
90		Installation Services at 395 Hudson Street - **Union Labor Rates**	---	
91		Installation Services at 205 East 42nd Street – **Non-Union Labor Rates**	---	
92		Installation Services at 555 West 57th Street **– Non-Union Labor Rates**		