



Tolman Engineering, Architecture & Surveying, PLLC
DBA: Patriot Design & Consulting, PLLC
500 Canal View Blvd. Suite 300
Rochester, NY 14623

RE: OPWDD Westfall Addendum #1
To: Jen Borgesi
From: Patriot Design and Consulting, PLLC.

OPWDD BRIDGING DOCUMENTS AMENDED:

1. The contractor is responsible for conducting their own field investigation in the boiler plant and coordinating the best tie in locations for steam and condensate.
2. Plumbing:
 - a. Section "5.5 HEALTHCARE PLUMBING FIXTURES/SPEC SECTION 224300":

Article 5.5.2.3:
DELETE the following section:
All water-closets shall be wall-mounted utilizing concealed wall carrier systems installed in the plumbing chase behind each closet and automatic.
REPLACE with the following:
All water-closets shall be bariatric on-floor style able to withstand loads up to 2,000 pounds with no measurable deflection and loads up to 5,000 pounds with no permanent damage. Water closet shall utilize concealed wall carrier systems installed in the plumbing chase behind each closet and automatic.
 - b. Section "7.5 HYDRONIC PIPING, VALVES & SPECIALTIES/SPEC SECTIONS 230523, 232113 & 232116":

Article 7.5.1.2.1:
DELETE the following section:
Piping 2-1/2" and smaller shall utilize threaded joints, and piping larger than 2-1/2" shall be fully welded.
REPLACE with following:
Piping 2-1/2" and smaller shall be type L copper with lead free soldered joint, and piping larger than 2-1/2" shall be fully welded.